

V2X Interoperability Test Plan

Wyoming Archer Test Track

www.its.dot.gov/index.htm

Final Test Plan – October 1, 2024
As Tested – November 15, 2024



U.S. Department of Transportation

U.S. Department of Transportation
Office of the Assistant Secretary for Research and Technology
Intelligent Transportation Systems Joint Program Office

U.S. Department of Transportation
Office of the Assistant Secretary for Research and Technology

Notice

This document is disseminated under the sponsorship of the Department of Transportation in the interest of information exchange. The United States Government assumes no liability for its contents or use thereof.

The U.S. Government is not endorsing any manufacturers, products, or services cited herein and any trade name that may appear in the work has been included only because it is essential to the contents of the work.

Technical Report Documentation Page

1. Report No. FHWA-JPO-24-148	2. Government Accession No.	3. Recipient's Catalog No.	
4. Title and Subtitle Test Plan for V2X Interoperability Testing		5. Report Date November 15, 2024	
		6. Performing Organization Code	
7. Author(s) Justin Anderson, Tony English, Kellen Shain, Spain Niemer, Brionna Hicks, and Benjamin Mangel		8. Performing Organization Report No.	
9. Performing Organization Name and Address Noblis, Inc. 500 L'Enfant Plaza, S.W., Suite 900 Washington DC, 20024		10. Work Unit No. (TRAIS)	
		11. Contract or Grant No.	
12. Sponsoring Agency Name and Address Federal Highway Administration 1200 New Jersey Ave., SE Washington, DC 20590-9898		13. Type of Report and Period Covered	
		14. Sponsoring Agency Code	
15. Supplementary Notes			
16. Abstract The following test plan is As Tested version of the Wyoming TIM interoperability test, the first (of four) interoperability tests that took place on October 7, 2024, and concluded on October 10, 2024, at the Archer Test Track 15 minutes outside of Cheyenne, WY. The purpose of this interoperability test is to test whether one participant's TIM can be received and correctly displayed by the other participants' OBUs. Six predefined scenarios were selected to test interoperability of OBUs and RSUs across different participants (CDOT, WYDOT, GDOT, USOT/Panasonic, THEA, Denso), and are as follows: 1) Base Case OBU Data Collection, 2) Weather Warning TIM, 3) Work Zone TIM, 4) Variable Speed Limit TIM, 5) End of Ramp Deceleration TIM, and 6) Pedestrian Crash Warning TIM. This document includes the following details: test equipment, features to be tested, features not to be tested, the approach, pass/fail criteria, suspension criteria, the test environment, roles and responsibilities, testing preconditions, the schedule, safety plan, risks, and contingencies, test cases, test procedures, modifications, and posttest analysis.			
17. Keywords Interoperability, Testing, V2X, Traffic Information Message, TIM, On-board Unit, OBU, Roadside Unit, RSU		18. Distribution Statement	
19. Security Classif. (of this report)	20. Security Classif. (of this page)	21. No. of Pages 162	22. Price

Form DOT F 1700.7 (8-72)

Reproduction of completed page authorized

Table of Contents

1	Introduction	8
1.1	Overview	8
1.2	Objectives	8
1.3	Assumptions	8
1.4	References	9
1.5	Document Overview	9
2	Test Equipment	11
2.1	Test Equipment OBU	11
2.2	Test Environment RSU	11
2.3	Test Item Installation	12
2.4	TIM Generation	12
2.5	Data Collection and Logging	13
3	Features to Be Tested	14
4	Features Not to Be Tested	15
5	Approach	16
5.1	V2X Interoperability Demonstration Planning	16
5.2	Test Readiness Review (TRR)	16
5.3	Test Execution	16
5.3.1	Installation and Checkout	16
5.3.2	Test Case/Test Procedure Dry Runs	17
5.3.3	Interoperability Demonstration Runs for Record	17
5.3.4	Interoperability Test Workbooks	17

5.4 Test Reporting	17
6 Pass/Fail Criteria	18
7 Suspension Criteria and Resumption Requirements	19
8 Test Environment	20
9 Roles and Responsibilities	21
10 Testing Preconditions	23
11 Schedule	24
12 Safety Plan, Risks, and Contingencies	29
13 Test Cases	31
13.1 Baseline OBU Data Collection	31
13.1.1 Test Objective	31
13.1.2 Test Description	31
13.1.3 Noise Baseline Measurement Test Description	32
13.2 Weather Warning TIM Test Cases	33
13.2.1 Weather Warning TIM Creation and Delivery	33
13.2.1.1 Test Objective	33
13.2.1.2 Test Description	33
13.2.1.3 Pass/Fail Criteria	35
13.2.2 Weather Warning TIM Revoke	35
13.2.2.1 Test Objective	35
13.2.2.2 Test Description	35
13.2.2.3 Pass/Fail Criteria	36
13.3 Variable Speed Limit (VSL) TIM	36
13.3.1 Variable Speed Limit TIM Creation and Delivery	36
13.3.1.1 Test Objective	36
13.3.1.2 Test Description	36
13.3.1.3 Pass/Fail Criteria	39
13.3.2 Variable Speed Limit TIM Update	39
13.3.2.1 Test Objective	39
13.3.2.2 Test Description	39
13.3.2.3 Pass/Fail Criteria	40
13.4 Work Zone TIM	41
13.4.1 Work Zone TIM Creation and Delivery	41
13.4.1.1 Test Objective	41
13.4.1.2 Test Description	41
13.4.1.2.1 Reduced Speed Zone	42

13.4.1.2.2	Right Lane Closed Ahead	44
13.4.1.2.3	Work Zone	46
13.4.1.3	Pass/Fail Criteria	48
13.5	End of Ramp Deceleration Warning (ERDW) TIM	48
13.5.1	ERDW TIM Creation and Delivery	48
13.5.1.1	Test Objective	52
13.5.1.2	Test Description	57
13.5.1.3	Pass/Fail Criteria	58
13.6	Pedestrian Crash Warning (PCW) TIM	58
13.6.1	PCW TIM Creation and Delivery	58
13.6.1.1	Test Objectives	59
13.6.1.2	Test Description	61
13.6.1.3	Pass/Fail Criteria	61
13.7	Edge Case TIMs	61
13.7.1	Message Count Turn-Over	61
13.7.1.1	Test Objective	61
13.7.1.2	Test Description	61
13.7.1.3	Pass/Fail Criteria	62
13.7.2	TIM Update to a Different Message Type with Same ID	62
13.7.2.1	Test Objective	62
13.7.2.2	Test Description	62
13.7.2.3	Pass/Fail Criteria	62
13.7.3	Message Priority	62
13.7.3.1	Test Objective	62
13.7.3.2	Test Description	63
13.7.3.3	Pass/Fail Criteria	63
13.7.4	Atypical Speed Limit Value	63
13.7.4.1	Test Objective	63
13.7.4.2	Test Description	63
13.8	Test Case Prioritization	64
14	Test Procedures	65
14.1	Baseline OBU Data Collection	65
14.1.1	Noise Baseline Measurements	66

14.2	Weather Warning TIM	67
14.2.1	Test Combinations Matrix	68
14.3	Variable Speed Limit TIM	69
14.3.1	Test Combinations Matrix	70
14.4	Work Zone TIM.....	71
14.4.1	Test Combinations Matrix	72
14.5	End of Ramp Crash Warning (ERDW) TIM.....	73
14.5.1	Test Combinations Matrix	75
14.6	Pedestrian Crash Warning (PCW) TIM	76
14.6.1	Test Combinations Matrix	77
14.7	Edge Case: Message Count Turn-Over	78
14.7.1	Test Case Matrix.....	79
14.8	Edge Case: TIM Update to a Different Message Type With Same ID	80
14.8.1	Test Case Matrix.....	81
14.9	Edge Case TIM: Message Priority	81
14.9.1	Test Case Matrix.....	83
15	Modifications Made to Test Plans and Procedures.....	84
16	Post Test Analysis.....	85

List of Tables

Table 1. References	9
Table 2. Test Equipment OBU	11
Table 3. Test Environment RSU	11
Table 4. Test Equipment Used for Interoperability Tests (X = Required, Y = Stretch Goal).....	14
Table 5. Risks and Contingencies	30
Table 6: Weather Warning TIM.....	34
Table 7: VSL TIM	37
Table 8: VSL TIM Update	40
Table 9: Reduced Speed TIM.....	43
Table 10: Lane Closed TIM	44
Table 11: Work Zone TIM	46
Table 12: Short Queue TIM	52
Table 13: Long Queue TIM.....	55
Table 14: Crosswalk TIM	60
Table 15. Test Case Prioritization.....	64
Table 16. Baseline OBU Data Collection Test Procedures Path.....	65
Table 17: Noise Baseline Measurements Test Procedures	66
Table 18. Weather Warning TIM Test Procedures	67
Table 19: Test Combinations Matrix	68
Table 20. Incident TIM Test Procedures.....	69
Table 21: Test Combinations Matrix	70
Table 22. Work Zone TIM Test Procedures.....	71
Table 23: Test Combinations Matrix	72
Table 24: End of Ramp Crash Warning Test Procedures	73
Table 25: Test Combinations Matrix	75
Table 26: Pedestrian Crash Warning Test Procedures	76
Table 27: Test Combinations Matrix	77
Table 28: Message Count Turn-Over Test Procedures	78
Table 29: Test Case Matrix.....	79
Table 30: TIM Update to Message Type Test Procedures	80
Table 31: Test Case Matrix.....	81
Table 32: TIM Message Priority Test Procedures	81
Table 33: Test Case Matrix.....	83
Table 34: Acronyms.....	86

List of Figures

Figure 1. Map of the Test Facility	20
Figure 2: Testing Schedule for Monday	24
Figure 3: Testing Schedule for Yunex	25
Figure 4: Testing Schedule for Danlaw	25
Figure 5: Testing Schedule for Commsignia	26
Figure 6: Testing Schedule for Iteris	26
Figure 7: Testing Schedule for Kapsch	27
Figure 8: Testing Schedule for THEA Yunex.....	27
Figure 9: Testing Schedule for Yunex	28
Figure 10: Testing Schedule for Commsignia	29
Figure 11. Baseline OBU Data Collection Path.....	32
Figure 12. Baseline Noise Measurement Locations	32
Figure 13. Weather Warning TIM location.	33
Figure 14. Variable Speed Limit TIM location.	37
Figure 15 Work Zone TIM location.....	42
Figure 16: Wyoming ERDW Lane Geometry Adaptation.....	49
Figure 17: Wyoming ERDW Lane Geometry Adaptation for Short Queue	50
Figure 18: Wyoming ERDW Lane Geometry Adaptation for Long Queue.....	51
Figure 19: Wyoming PCW Lane Geometry Adaptation	58
Figure 20: WY PCW Test Site Configuration	59

Revision History

Date	Rev.	Section(s)	Description
8/13/24	-	-	Initial Outline of V2X Interoperability Test Plan
8/14/24	-	1, 13, 14	Drafted Test Cases and Intro
8/21/24	-	1, 2, 4, 5, 9, 10, 11, 13	Addressed Tony English' comments
8/27/24	-	-	General Updates
9/03/24	-	2.1, 2.2, 3	Test Equipment information
9/13/24	-	14	Test Procedures
9/25/24	-	12	Safety Test Plan
9/30/24	-	-	Final Editorial Edits
10/23/24	-	-	Edited schedule and updated test cases and procedures to reflect testing
11/15/24	-	-	Final edits and 508 compliance

1 Introduction

1.1 Overview

With the accelerating deployment of Vehicle-to-Everything (V2X) technologies there is the potential for different interpretations of key V2X standards to introduce interoperability issues between operational deployments. Interoperability is critical to the National Deployment of V2X and the US Department of Transportation's (USDOT) V2X Deployment Plan specifically calls out that criticality. To address potential interoperability issues, Interoperability Tests need to be conducted with operational deployments now to either validate that V2X standards are being interpreted correctly or identify issues and address them in standards before there are millions of devices deployed. The V2X Deployment Cohort, which meets monthly and consists of 30+ federally funded V2X deployments, identified testing around traveler information messages (TIM) as their highest priority to test in the near term. This Interoperability Test Plan 1 outlines the test cases and procedures for the end-to-end interoperability testing process around TIMs with stretch goals for SCMS and cellular tests.

This **As Tested Version** of the interoperability test plan reflects changes to the test schedule, equipment, edge cases, and test procedures based on real-time feedback from deployers, manufacturers, and test facilitators.

1.2 Objectives

The goal for the Interoperability Test Technical Support task order is to test TIM, SCMS, and newer cellular technologies with Infrastructure Owner Operators (IOOs). The Interoperability Test will be designed to validate that the operational configuration of V2X devices and V2X communications between different IOOs and deployment agencies are interoperable with each other and to find potential areas where there may be interoperability issues.

The operational configuration and communication will be tested between different site's Onboard Units (OBUs) and V2X interactions between selected OBUs and Roadside Units (RSUs). RSUs should be able to transmit the correct TIM for the appropriate test case. OBUs should be able to receive the TIM and display it only in the valid direction and Geographic Validity Region.

1.3 Assumptions

To demonstrate interoperable connected vehicle applications, many supporting connected vehicle technology elements need to be included:

- OBUs and RSUs need to use credentials obtained from the same security credential management system (SCMS), as defined in IEEE 1609.2.1, to include signatures with messages and validate received messages as necessary.
- Positioning accuracy must satisfy SAE J2945/1. It was agreed that the tests and demonstration of Infrastructure to Vehicle (I2V) interoperability will take place in an "open sky" environment with no

site-specific position augmentation. This test will focus on I2V TIMs. No Vehicle to Vehicle (V2V) testing is planned.

- Although the focus of the Interoperability Test is on light-duty vehicle interoperability, the presence of optional data content in device messages designed for trucks or other vehicle classes should not affect basic interoperability of messages and credentials.

1.4 References

Table 1 provides documentation of previous works that were used in the creation of this test plan:

Table 1. References

Document	Title
Interoperability Test Cases.zip (Multiple files)	Wyoming Interoperability Test Cases
CVP Phase 2 Test Plan	Connected Vehicle Pilot Phase Interoperability Test – Test Plan
TIM Definitions PowerPoint	TIM Definitions for Interoperability Testing
TIM Standardization PowerPoint	TIM Standardization

1.5 Document Overview

This document identifies and describes the organization, resources, activities, methods, and procedures that will be used during V2X Interoperability Testing. Sections included in this Test Plan include:

- **Section 1: Introduction** – States the purpose of this test plan, provides references to other documents relevant to this project, and identifies the scope of this plan.
- **Section 2: Test Equipment** – Identifies the equipment that will be tested within the scope of this test plan.
- **Section 3: Features to Be Tested** – Identifies the features of the test items that will be tested.
- **Section 4: Features Not to Be Tested** – Identifies any features of the test items that will not be tested.
- **Section 5: Approach** – Provides the overall test strategy for V2X Interoperability Testing. It defines the overall rules and processes that will be used.
- **Section 6: Pass/Fail Criteria** – Identifies the completion criteria for the test items included in the test plan.
- **Section 7: Suspension Criteria and Resumption Requirements** – Specifies what constitutes stoppage for a test or series of tests.
- **Section 8: Test Environment** – Describes the environment that V2X Interoperability Testing will be conducted within.
- **Section 9: Roles and Responsibilities** – Identifies who the responsible party is for areas of the test.

-
- **Section 10: Testing Preconditions** – Identifies the key tasks that must be complete before V2X Interoperability Testing can be conducted.
 - **Section 11: Schedule** – Identifies the timeline for the key tasks and test items included in the test plan.
 - **Section 12: Safety Plan, Risks, and Contingencies** – Identifies safety considerations for testing and the overall risks to the project with emphasis on the test processes.
 - **Section 13: Test Cases** – Provides the test cases for each of the tests that will be accomplished during testing.
 - **Section 14: Test Procedures** – Provides the detailed step-by-step procedures for each test case.
 - **Section 15: Modifications Made to Test Plans and Procedures** – Provides a section to document any modifications to the Test Plan and procedures while the Interoperability Test is underway.
 - **Section 16: Post Test Analysis** – Provides information on how the collected will be analyzed after the completion of the test.

2 Test Equipment

2.1 Test Equipment OBU

Table 2. Test Equipment OBU

Participant	Device	Vendor	Model #	SCMS Enrollment	Quantity
WYDOT (Neaera)	OBU	Commsignia	ITS-OB4 Qualcomm	ISS	1
WYDOT (Neaera)	OBU	Commsignia	ITS-OB4 Qualcomm	Autocrypt	1
GDOT	OBU	Cohda	MK6	ISS	1
UDOT (Panasonic)	OBU	Ficosa	TCU-CARCOM-G1	ISS	1
UDOT (Narwhal)	OBU	Commsignia	ITS-OB4-M	ISS	1
UDOT (Narwhal)	OBU	Commsignia	OBU Lite	ISS	1
UDOT (Narwhal)	OBU	Cohda	MK6	ISS	1
THEA (DENSO/HNTB)	OBU	DENSO	Hercules	ISS	3
OmniAir	OBU	Iteris	-	ISS Test Cert	1
OmniAir	OBU	Kapsch	CBX-9360	ISS Test Cert	1
OmniAir	OBU	Keysight	Wavebee	ISS Test Cert	1
OmniAir	OBU	Commsignia	ITS-OB4	ISS Test Cert	1

2.2 Test Environment RSU

Table 3. Test Environment RSU

Participant	Device	Vendor	Model #	SCMS Enrollment	Quantity
WYDOT (Neaera)	RSU	Commsignia	ITS-RS4 Qualcomm	ISS	1
CDOT (Neaera)	RSU	Commsignia	ITS-RS4 Qualcomm	Autocrypt	1
CDOT (Neaera)	RSU	Yunex	RSU2X	ISS	1
GDOT	RSU	Danlaw	RouteLink	ISS	1
UDOT (Panasonic)	RSU	Kapsch	RIS-9260	ISS	1
UDOT (Narwhal)	RSU	Kapsch	RIS-9360	ISS	1
UDOT (Narwhal)	RSU	Commsignia	ITS-RS4-M	ISS	1
THEA (DENSO/HNTB)	RSU	MobiQ	5940 Evaluation Kit	ISS	1

2.3 Test Item Installation

V2X Interoperability Test site equipment expectations include:

- Equipment shall be delivered to Vince Garcia at WYDOT by September 30th to provide enough time for initial equipment installation. Shipping address and contact info:

CC: Vince Garcia

Wyoming Department of Transportation

5300 Bishop Blvd, Cheyenne, WY 82009

2.4 TIM Generation

The following are the data needs for TIMs to be used at the Archer Test Track:

- Identification of which RSUs should be used to broadcast the TIM.
- Identification of whether production certifications are okay to use.
- ASN.1 code to send to the RSU using SNMP per CTI 4001.
- The ASN.1 code should be built for the road at the Archer Test Track.
- The TIM shall be saved in the following tool so that TIM parameters can be edited day of testing: Connected Vehicle TIM Message Creator (connectedvcs.com).
- MUTCD graphics (PNG/JPG) shall be used for OBUs.
- The OBUs shall use an ITIS sentence (preference for ITIS codes only and no text) to identify the TIM to MUTCD graphic.
- Identification of directionality to drive for the expected driver alert in the geofence.
- Identification of directionality to drive and not expect the driver alert in the geofence (if applicable).
- The participant shall be prepared to generate any updates and expiration that are needed to test for ASN.1.

2.5 Data Collection and Logging

Each test participant will need to have a way to log data on the OBU. The minimum data needed to provide is:

- 1) Location and time for each received TIM, to include TIM.
- 2) Location, time and heading (using BSM at time of driver alert for example) of vehicle with each driver alert for each TIM, to include TIM.

The data logs should be provided in a way that does not require any vendor tools to view nor to perform data analytics. The data should be provided on a shared cloud data system (Google Drive, OneDrive, S3 bucket, etc.). Flash drives will be provided as well for data collection.

Update: An Amazon Web Service (AWS) Cloud, hosted by FHWA and managed by Leidos, was established following the conclusion of the testing. Each full participant of the Interoperability Testing was provided a login an AWS link to upload their data for analysis.

3 Features to Be Tested

V2X Interoperability Testing will focus on demonstrating interoperability between different IOOs and deployment agencies. As mentioned previously, the V2X Deployment Cohort identified TIM messaging applications as the top priority for interoperability testing. This test is designed to validate the operational configuration and communication between RSUs and OBUs for sending TIMs. Three main test cases have been designed for common TIM warning formats—Weather, Work Zone, and Variable Speed. Additional TIMs may be tested if time permits. As a stretch goal each TIM test, in addition to PC5 (LTE-V2X), will also be tested with MEC (Network-V2X). Additionally, the Tampa Hillsborough Expressway Authority (THEA) has identified an End of Queue Warning for Exit Ramps and a Pedestrian Crash Warning application that produces TIMs. The TIM messaging aspects of those applications will be tested, bringing the total number of test cases to five.

Table 4. Test Equipment Used for Interoperability Tests (X = Required, Y = Stretch Goal)

Participant	Baseline	Weather TIM	Work Zone TIM	Variable Speed TIM	ERDW TIM	PCW TIM
WYDOT	X	X	X	X	Y	Y
CDOT	X	X	X	X	Y	Y
GDOT	X	X	X	X	Y	Y
UDOT	X	X	X	X	Y	Y
THEA	X	X	X	X	Y	Y
DENSO	X	X	X	X	Y	Y

Additional features were tested as “edge cases”. These edge cases were discussed by the participant group and added day of. Details of these edge cases are located in section 13.7.

4 Features Not to Be Tested

This round of interoperability testing is the first of several rounds (exact number of tests TBD), so this test is limited to TIMs. Future rounds of testing will likely have an expanded scope and include other message types in addition to TIMs.

The following features are not within scope of this testing:

- Negative testing of any of the applications.
- Performance testing of any of the applications.
- Road Safety Messages.
- Forward Collision Warning.
- Electronic Emerging Brake Light.
- Signal Phase and Timing.
- Connected Intersections testing.
- Pedestrian Safety Messaging (PSM).

5 Approach

This section covers the approach for test planning as well as the approach for conducting the test itself.

5.1 V2X Interoperability Demonstration Planning

The Interoperability Technical Working Group (ITWG), led by Justin Anderson, met weekly to determine and reach a consensus on the scope for the first Interoperability Test. The group decided that TIMs would be the best message type to test first given their widespread use and relative ease of implementing and testing given the short lead time for the first test.

5.2 Test Readiness Review (TRR)

During the week prior to V2X Interoperability Testing, there will be a Test Readiness Review (TRR) to review key pre-conditions in Section 10 that must be met before the demonstration can be held and to officially approve of the Test Cases and Test Procedures. Participating deployments will send their devices to the Interoperability Testing Environment to be delivered by September 30th. Progress towards test readiness will be reviewed at the V2X Cohort meetings.

5.3 Test Execution

The execution of V2X Interoperability Testing will last for four days and will be split into three phases: (i) Installation and Checkout, (ii) Test Case/Test Procedure Dry Runs, and (iii) Interoperability Demonstration Runs for Record. The detailed schedule for these events will be captured in the Interoperability Test Workbook that is distributed separately from this document and will be made available to all test participants. Throughout all three phases, a Test Director, whose role is described in Section 9, will be the final authority on test activities including confirming completion of each phase and initiation of the subsequent phase. Test workbooks will be developed and distributed for guidance and test recording.

5.3.1 Installation and Checkout

The first phase will be installation and checkout. This phase will be accomplished in accordance with Section 2.3 of this document, with installation of RSUs and other equipment leading up to the Interoperability Test, and the morning of Monday October 7th scheduled for the final checkout of the system. It is anticipated that participants will send devices to the Interoperability Test Environment to be received by WYDOT by September 30th. The contractor shall assist in the checkout of Test Equipment and Test Environmental setup. At the completion of the installation and checkout, each site must confirm their devices under test are installed and operating correctly with verified conformance to prerequisite lower layer communication standards and security.

5.3.2 Test Case/Test Procedure Dry Runs

The second phase of test execution includes a dry run of the test cases and test procedures that are demonstrated during the interoperability test. Once the tests have been successfully run and devices and procedures appear to work correctly and demonstrate the necessary functionality, test execution moves to the third phase. If there are any issues during the dry runs, Noblis works with USDOT and test participants to quickly triage and determine adjustments or revisions to the test cases/procedures and document for the record testing phase.

5.3.3 Interoperability Demonstration Runs for Record

The third phase of test execution includes the official interoperability testing runs for record. During the runs for record phase, all test cases are executed per a USDOT approved schedule. During testing, Noblis, the technical support contractor for this task, appoints personnel to track a master copy of the workbook, track the status of each test executed, officially record pass/fails, note any issues or discrepancies. Issues and discrepancies will be discussed with the Test Director and test participants to determine whether the test schedule needs to be adjusted to provide time to resolve the issue or if it is minor enough for testing to continue as scheduled.

5.3.4 Interoperability Test Workbooks

Interoperability test workbooks in electronic form are prepared for key test participants and delivered 10 business days before the start of each test. Noblis creates at least 20 hard copies to be available on the test days. The workbooks include the following:

- List of key points of contact with contact numbers
- Test schedules
- Test procedures for participants to track steps during testing with a notes column to make notes on any issues or discrepancies found during testing
- Expected outcomes for each test

5.4 Test Reporting

After the successful conclusion of V2X Interoperability Testing, a Test Report will be developed that provides an overview of all the tests executed and their results and publicly posted to the ITS JPO's V2X Testing website. The Test Report will also provide an overview of the data collected and how to request/receive access to that data. Finally, it will provide lessons learned from interoperability testing as well as any issues encountered and how those issues were resolved/will be resolved.

6 Pass/Fail Criteria

The Pass/Fail criteria for each test case is listed in Section 13: Test Cases. For a Test Case to pass, it must fulfill all pass criteria in that test case, or all threshold criteria in those test cases that have threshold and objective criteria. Partially meeting pass criteria will result in a failure for that test case, however retesting may only require retesting the failed functionality.

7 Suspension Criteria and Resumption Requirements

There are multiple possible events that could require suspension of testing. The most critical being safety of life issues either associated with an issue with the devices or if conditions in the test environment become hazardous to the vehicles operating within it (e.g., inclement weather). Other events could be inoperable devices or multiple devices experiencing critical functional issues. The Test Director will make the final decision on whether to suspend or resume testing. For testing to resume, the issue(s) that caused the suspension of testing must be confirmed to be resolved by all stakeholders involved with the test as well as the Test Director.

8 Test Environment

Testing will be conducted at the Archer Complex in Cheyenne, Wyoming. Figure 1 depicts a map of the test facility including key infrastructure (e.g., location of TIM geofences, conference room, and rest rooms) currently located at the Test Facility.




Figure 1. Map of the Test Facility

9 Roles and Responsibilities

The following roles are defined in this Test Plan.

Test Sponsor – Justin Anderson, DOT – ITS JPO

The Test Sponsor is responsible for:

- Managing the technical support resources provided for testing;
- Approving test plans, procedures and reports;
- Ensuring coordination between the test participants; and
- Ensuring test plans, reports, lessons learned and data are publicly posted and available.

Test Director – Tony English, Darren Weibler Assisting

The Test Director is responsible for managing the execution of testing. The Test Director is responsible for:

- Managing the execution of each Test Execution phase;
- Approving the completion of each test execution phase and will approve the initiation of the next phase;
- Suspending/resuming testing, as necessary, during test execution;
- Approving changes to the test schedule during the test execution phase; and
- Approving the end of testing.

Test Coordinator – Noblis

The Test Coordinator is responsible for:

- Maintaining and updating the V2X Interoperability Test Plan;
- Working with the applicable stakeholders to get inputs for gaps/updates to the test plan;
- Tracking the status of V2X Interoperability Test Planning/Test Readiness;
- Supporting the execution of interoperability testing by tracking progress of each participant through each execution phase, tracking and redlining test procedures as they are run, and tracking and documenting issues and lessons learned; and
- Coordinating the development of V2X Interoperability Test Report.

Participant Test Leads – Participant 1: WYDOT Michael English, Participant 2: CDOT Drew Johnston, Participant 3: GDOT, Participant 4: UDOT/Panasonic, Participant 5: THEA Steve Novosad, and Participant 6: DENSO Jason Graves

The Participant Test Leads are responsible for:

- Providing site specific inputs to the V2X Interoperability Test Plan;
- Reviewing the V2X Interoperability Test Plan and providing comments;
- Providing site specific devices, installation kits, and other necessary equipment for the demonstration;
- Approving the installation and functional checkout of their site-specific devices;
- Troubleshooting issues found with site specific devices and/or identifying the subject matter experts necessary to troubleshoot their site-specific devices;
- Collecting data from site specific devices;
- Providing site specific inputs to the V2X Interoperability Test Report; and
- Reviewing the V2X Interoperability Test Report and providing comments.

Test Support Personnel – Brandon Payne, Rick Smith and Daniel Stephenson to support TIM updates to RSUs for all devices.

The Test Team shall be responsible for:

- Providing inputs to the Interoperability Test Plan, specifically identifying the optimal locations to execute the Test Cases and Procedures in Sections 0 and 0 of this document;
- Preparing the test environment;
- Driving the vehicles through the test environment;
- Conducting test support roles such as Flagger and Manual Signal Operator; and
- Operating test environment specific devices/equipment.

USDOT Representative Team – Kate Hartman, Justin Anderson

The USDOT Representative Team shall be responsible for:

- Reviewing, commenting on and approving the V2X Interoperability Test Plan;
- Witnessing the execution of the tests;
- Coordinating/Approving test support; and
- Reviewing, commenting on and approving the first V2X Interoperability Test Report.

V2X Device Vendors – Commsignia, Ficosa, Danlaw, Kapsch, Cohda, Iteris

The V2X Device Vendors shall be responsible for:

- Providing test support and assistance to the Participant Test Leads;
- Supporting device installation and checkout as necessary; and
- Supporting troubleshooting of issues found during testing as necessary.

10 Testing Preconditions

The following preconditions must be met before V2X Interoperability Testing can begin:

- All stakeholders must approve the Test Plan;
- All devices must be enrolled/have production certificates from the SCMS System;
- All devices must be in the OmniAir certification process;
- Test environment is available and ready for V2X device installation;
 - Drivers are available and familiar with test cases and procedures;
 - Testing locations are available and have staff to help assist when necessary;
 - Infrastructure is available and configured;
 - Test Plan has been coordinated with facilities and neighbors;
 - Flaggers (if necessary) have been identified and are available;
 - Meeting rooms and other facilities are reserved;
 - Test Equipment is available and functional;
 - Wireless Packet Sniffers;
 - Vehicles;
 - Potentially conflicting safety systems (e.g. automated steering) disabled;
 - TIMs have been generated for each RSU location.

11 Schedule

This section contains a detailed test schedule based on the deployment sites providing their OBUs and RSUs a minimum of two weeks before the start of formal testing. This schedule assumes using a single OBU installed in a single vehicle for each test run. A basic assumption of 10 minutes per test run is assumed for these schedules, however as Test Staff install devices and conduct dry runs, this assumption may be revised. The following is a more detailed breakout of the test schedule. The numbers above the TIM messages indicate the row in the TIM table in the RSU that was used for that message.

- **Test Readiness Review –**
 - Review Test Preconditions in Section 10 of this document and ensure all are either met or on track to be met before October 7.
 - All stakeholders approve the final test plan.
 - All Deployment programs confirm that they are still ready and able to participate in interoperability testing and that devices are received no later than September 30.
- **Day 1: Monday**

Roadside unit (RSU) setup in the morning, followed by baseline testing to check that RSUs publish traveler information messages (TIMs) generated by WYDOT and all on-board units (OBUs) receive/display TIMs successfully. In the afternoon, sent out v2 TIMs adding revoke times (red bar indicates when) to each. Testing Weather Warning (W), Speed Limit (SL), Reduced Speed Zone (RSZ), Lane Closure (LC), and Work Zone (WZ) TIMs. No OBU should display a message after the revoke time. Testing on Monday used a Commsignia RSU provided by the WYDOT team.

		2100_rsu Commsignia					
		21	31	41	42	43	71
Local		W	SL	RSZ	LC	WZ	W
8:00		v1	v1	v1	v1	v1	
8:30							
9:00							
9:30							
10:00							
10:30							
11:00							
11:30							
12:00							
12:30							
13:00							
13:30			v2				
14:00		v2		v2	v2	v2	
14:30							
15:00			v3				
15:30							
16:00							v1
16:30							

Figure 2: Testing Schedule for Monday

- **Day 2: Tuesday**

Yunex RSU Testing Schedule: Testing if W, SL, RSZ, LC, and WZ TIMs generated by WYDOT are received/displayed correctly by all OBUs from the Yunex RSU provided by the WYDOT team. V2 TIMs were sent out with a revoke message, except for SL which used the V3 as a revoke message. No OBU should display a message when the revoke message has been sent out.

260_rsu Yunex						
	21	31	41	42	43	
	W	SL	RSZ	LC	WZ	
v1		v1	v1	v1	v1	8:00
						8:15
		v2				8:30
v2						8:45
		v3	v2	v2	v2	9:00
						9:15
						9:30

Figure 3: Testing Schedule for Yunex

Danlaw RSU Testing Schedule: Testing if W, SL, RSZ, LC, and WZ TIMs generated by WYDOT are received/displayed correctly by all OBUs from the Danlaw RSU. V2 TIMs were sent out with a revoke message, except for the SL TIM which used the V3 message as the revoke. No OBU should display a message when the revoke message has been sent out.

268_rsu Danlaw						
	21	31	41	42	43	
	W	SL	RSZ	LC	WZ	
9:45						
10:00	v1	v1	v1	v1	v1	
10:15						
10:30						
10:45	v2	v2				
11:00		v3	v2	v2	v2	
11:15						
11:30						

Figure 4: Testing Schedule for Danlaw

Commsignia (Autocrypt) RSU Testing Schedule: Testing if W, SL, RSZ, LC, and WZ TIMs generated by WYDOT are received correctly by all OBUs from the Commsignia RSU enrolled with Autocrypt SCMS provided by the WYDOT team. V2 TIMs were sent out with a revoke message, except for the SL TIM which used the V3 message as the revoke. No OBU were expected to display a message because the RSU was enrolled in an Autocrypt certificate and all OBUs were enrolled in ISS certificates.

		266_rsu Kapsch Panasonic						266_rsu Kapsch Narwall	
		21	31	40	41	42	43	71	81
Local		W	SL	RSZ1	RSZ2	LC	WZ	W	SL
8:00		v1	v1	v1	v1	v1	v1		
8:15									
8:30			v2						
8:45									
9:00		v2							
9:15			v3						
9:30				v2	v2	v2	v2	v2	v2
9:45									
10:00									

Figure 7: Testing Schedule for Kapsch

THEA Yunex RSU Testing Schedule: Testing if short queue, long queue, and pedestrian TIMs generated by THEA are received/displayed correctly by all OBUs from the Yunex RSU provided by the THEA team.

		THEA Yunex				
		21	31	41	42	43
10:00						
10:15	short queue					
10:30						
10:45	long queue					
11:00						
11:15						
11:30	pedestrian					
11:45						
12:00						

Figure 8: Testing Schedule for THEA Yunex

Yunex RSU Testing Schedule: Testing if W, SL, and RSZ TIMs generated by WYDOT are received/displayed correctly by all OBUs from the Yunex RSU provided by the CDOT (Neaera) team. V1 TIMs were sent out with initiation times (green bar indicates when). V2/V3 TIMs were sent out starting at 14:00 local with a revoke message included to begin broadcasting 14:45 local. No OBU was expected to display a message before the initiation time or after the revoke time.




Figure 9: Testing Schedule for Yunex

- **Day 4: Thursday**

Edge Case on Commsignia RSU Testing Schedule: Edge case testing on W, SL, RSZ, and WZ TIMs generated by WYDOT are received/displayed correctly by all OBUs from the Commsignia RSU provided by the WYDOT team. Testing occurred throughout the morning.

- The W1 TIM edge case tested what occurs when the message count turns-over from 127 to 0.
- The W2 TIM edge case tested what occurs when a W TIM is set to update to a WZ TIM with the same ID.
- The SL1 & SL2 TIMs were used to test message priority and its impact on an OBU's display of TIMs.

Edge case test on backwards path (clockwise around the Archer Test Track) RSZ TIM generated by WYDOT are received/displayed correctly by all OBUs from the Commsignia RSU provided by the WYDOT team. Testing occurred throughout the morning.

		2100_rsu Commsignia									
		21		22		31		32		71	
Local		W1		W2		SL1		SL2		RSZ	
8:00		v127				v1		v2		v1	
8:15						p0		p0			
8:30											
8:45											
9:00		v0									
9:15											
9:30								v3			
9:45								p7			
10:00				v1							
10:15											
10:30											
10:45				v1							
11:00						v1		v3			
11:15						p7		p0			

Figure 10: Testing Schedule for Commsignia

12 Safety Plan, Risks, and Contingencies

Conducting the Interoperability Testing safely is of utmost importance to the USDOT, and safety should be taken seriously by each participant. The testing location is an open, public road that experiences low levels of traffic. Since it is an open, public road, all participants should follow the normal rules of the road.

It is also expected that the drivers, or licensed operators, and vehicles have the necessary insurance to drive on normal roads. The participants should remember and implement the following during testing:

1. Follow all rules of the road (speed limits and direction of driving)
2. Do not stop on roadways
3. Do not walk on roadways
4. No harsh braking or acceleration
5. Pedestrian should wear a vest when testing PCW TIM

Table 5 provides the high-level risks and contingencies identified with conducting this Interoperability Test.

Table 5. Risks and Contingencies

Risk	Likelihood	Severity	Contingency
Foul Weather	Medium	Low	The most likely weather occurrence during the likely timeframe of the interoperability test is wind. Historically, there is a remote chance for snow during this time of year. The test team will monitor weather forecasts leading up to the interoperability test and the Test Director will make final decisions on if the weather conditions are safe enough to conduct testing.
EMI Interference	Low	High	There is the possibility that neighboring facilities may conduct activities that could interfere with communications in the V2X spectrum. A spectrum analyzer will be available for use and beginning of day and end of day measurements will be taken to ensure there are no other devices that could interfere with devices operating in the 5.895-5.925 GHz range.
Test Vehicle Mechanical Breakdown	Low	Low	The Test Facility maintains a fleet of test vehicles and regularly conducts maintenance on them. If a test vehicle experiences mechanical issues the Test Facility will investigate the issue while testing can continue using the other vehicles with equipment installed. If the vehicle cannot be repaired in time, the Test Facility will determine the feasibility of installing the OBU in a different vehicle.

13 Test Cases

13.1 Baseline OBU Data Collection

13.1.1 Test Objective

The objective of the Baseline OBU Data Collection test is to collect data (Driver Alerts, BSMs, and TIMs) from OBUs from each participant installed on a vehicle to create a baseline of how devices perform. If the participant can provide their devices early, this testing may be accomplished prior to their arrival for testing. Otherwise, this test would be the first test accomplished and would be accomplished in conjunction with the Installation and Checkout Phase.

To collect baseline conditions, SCMS production certificates will be used for TIM generation on RSUs and OBUs. All broadcast TIMs will be signed unless testing receipt security on OBUs.

An additional baseline measurement is the Noise Baseline Measurement collected by Leidos. Noise baseline measurements in the V2X communication band will be conducted at the beginning of each test day. The target is to evaluate any possible interfering signal within the C-V2X band that could affect the testing process. Collecting these measurements will provide more insights in terms of communication preferences (PER, time to action, latency, etc.) and characterize and understand the information flow between devices related to TIMs. The measurements will be utilized in the future for AI modeling/training if applicable

13.1.2 Test Description

Each vehicle travels the path shown in Figure 11. Baseline OBU Data Collection Path from Point A to Point B. The vehicle travels this path three times. The OBUs will collect driver alerts, BSMs, and TIMs that caused alert. All logs will include ms UTC time. At the conclusion, it is verified that TIMs were collected from each participant. These logs will be uploaded to participant selected cloud drive (OneDrive, Google Drive, S3 bucket or the like) for review by test admin team.

* **Note:** Participant vehicles may be rental cars or agency-owned vehicles from the deployment agencies and V2X device vendors.




Figure 11. Baseline OBU Data Collection Path

13.1.3 Noise Baseline Measurement Test Description

The Noise level will be measured using a FieldFox connected to an LNA. The measurements will be taken at five different locations over the test track as shown in figure below. All collected data (Equipment snapshot) will be uploaded to the cloud storage and marked by date and time.




Figure 12. Baseline Noise Measurement Locations

13.2 Weather Warning TIM Test Cases

13.2.1 Weather Warning TIM Creation and Delivery

13.2.1.1 Test Objective

The objective of the Weather Warning TIM creation and delivery test case is for multiple deployments to generate a weather warning TIM for the same weather warning according to their operational processes, distribute that TIM to an RSU and have multiple different vendor OBUs drive past the RSU, store the TIM and then display the TIM only when it meets the criteria for display. The intent is to demonstrate that the TIM messages generated by each of the participating deployments can be received and displayed with the relevant information by each of the different OBU models. SCMS production certificates will be used for the generation of TIMs on RSUs and validated on the OBUs.


13.2.1.2 Test Description

The initial step of this test will be for all participating deployment agencies to generate a weather warning TIM as described below:



Figure 13. Weather Warning TIM location.

Table 6: Weather Warning TIM

Value	Column 1	Column 2
msgCnt	1	-
packetID	8D442EF0010C6B1A01	-
dataframe	-	-
-	content	advisory
-	itis-codes	4868
Region	-	-
-	anchor	Lat: 41.153400 Lon: -104.657587
-	lane-width	50 m
-	directionality	3
-	closed-path	false
-	description	path
-	direction-mask	"1111000011110000"
suggested icon		-

The packetID and message count together uniquely identify the TIM. The provided packetID is an example value. For this initial TIM version, the message count is set to 1. Subsequent updates or revocations of this TIM will increment the message count. A depiction of the Geographic Validity Region of the TIM is shown in the figure above. The validity region geofence is defined as a path along the roadway with a 50-meter lane width. Note, the heading direction mask defines valid vehicle headings to provide this alert. In this case a driver alert for this TIM should be displayed in either direction of travel through the TIM geofence. A suggested driver display icon is provided; this is the suggested graphic to display for the driver if the OBU provides such a display.

The following hex string is a signed and encoded version of the initial Weather Warning TIM described above:

```
0381004003807b001f78701575588d442ef0010c6b1a010f775d9b0301c271635d816742b80ffff93f42baac
21c0a007f8da7bb7f74107963d197920a2c60000000271635d816742b809388de1e02110047671d088a0
d65048ed6d7824143342117657e409678b5e0476353fc26c52d781393d46b09fb2a7f8000004c10f775d9b
06001830002519767c5327f0002520c01ff120081010100030180c620fb90caad3b9c50820851142251286
5acbd396921000326e52b7883279c83010180034801010001838183748c51728ff0d88dad3ecd5a87c471
```

e77fb53eb57db0dad64fe5c85dd5c59e5280805c022422a198a55df34d44d29a923feb3c22cf5e6326fdd010d8eedf67f1d55b7c3bad69cb4d46ea8eb928c9ccb8445ef4084d92c65b1e3767e7943fddd343e

During the tests, the start time and duration will be configured for the broadcast TIMs to support a series of updates and revocations.

Each deployment will then either deploy the message directly to an RSU in the test environment or provide the message to the deployment agency that controls that RSU for deployment. The deployment agency will also detail whether:

- They sign their TIM messages at the TMC
- They sign their TIM messages at the RSU (expected way for most testing)
- They sign their TIM messages at the TMC, send to the RSU, RSU validates the signature on the TIM and then strips the certificate and signs with its certificate.

Vehicles with different OBU models will start driving at the top of the oval track from the north most roundabout, traveling counterclockwise around the oval. Observers will note that the Weather Warning TIM should appear on the HMI as the vehicle enters the geofence in the northwest quadrant of the oval track and should note the approximate time and location when the TIM appeared.

The vehicles will continue around the oval to complete the following two TIM tests then turn around through the north most roundabout and drive through the Weather Warning TIM geofence traveling clockwise around the oval (after first passing through Variable Speed Limit and Work Zone TIMs). Observers will note that the Weather Warning TIM should appear on the HMI as the vehicle enters the geofence from the west side and should note the approximate time and location when the TIM appeared.

13.2.1.3 Pass/Fail Criteria

- RSUs correctly broadcast the Weather Warning TIM.
- OBUs receive the Weather Warning TIM and display it driving either way in the Geographic Validity Region.

13.2.2 Weather Warning TIM Revoke

13.2.2.1 Test Objective

The objective of the Weather Warning TIM Revoke test case is for deployments to revoke their original Weather Warning TIM message and verify that the OBU updates the TIM message that resides in their devices. Revoking a TIM message means updating the TIM message and setting the expiration time to within 5 minutes of the current time.

13.2.2.2 Test Description

To revoke the Weather Warning TIM deployments will update the originally generated Weather Warning TIM with an expiration time (i.e. validity time) at some fixed future time so that OBUs will not receive the

message. It should be noted that for operational TIMs, once the TIM validity time is reached the message becomes invalid within 5 minutes of the current time. The packetID of the TIM should remain the same as the original Weather Warning TIM, but the message count must be incremented to indicate that this newly generated TIM supersedes the original Weather Warning TIM.

Deployments will update their Weather Warning TIM with this validity time change and resend that TIM to the test environment RSUs. Vehicles may need to remain running between the original test and this revoke test to ensure the original TIM remains on the OBU and that the revocation TIM supersedes the original version. The vehicles will then travel the same pattern as described in Section 13.2.1.2, however in this case, a message should never appear on the HMI since the current time is outside the validity of the TIM. As an additional check, inspection of the OBU logs should show the TIM was updated internally to the latest version.

13.2.2.3 Pass/Fail Criteria

- RSUs correctly broadcast the updated Weather Warning TIM.
- OBUs receive the Weather Warning TIM and do not display it.
- OBUs update their internal saved version of the Weather Warning TIM.

13.3 Variable Speed Limit (VSL) TIM

13.3.1 Variable Speed Limit TIM Creation and Delivery

13.3.1.1 Test Objective

The objective of the Variable Speed Limit TIM creation and delivery test case is for multiple deployments to generate a variable speed warning TIM for the same speed limit warning according to their operational processes, distribute that TIM to an RSU and have multiple different vendor OBUs drive past the RSU, store the TIM and then display the TIM only when it meets the criteria for a Driver Alert. The intent is to demonstrate that the TIM messages generated by each of the participating deployments can be received and displayed with the relevant information by each of the different OBU models.

13.3.1.2 Test Description


The initial step of this test will be for all participating deployment agencies to generate a Variable Speed Limit TIM as described below:



Figure 14. Variable Speed Limit TIM location.

Table 7: VSL TIM

Value	Column 1	Column 2
msgCnt	1	-
packetID	8D442EF002FC6B1B01	-
dataframe	-	-
-	content	speedLimit
-	itis-codes	268, 12599, 8720
region		
-	anchor	Lat: 41.1513384 Lon: -104.6444217
-	lane-width	50 m
-	directionality	3
-	closed-path	false
-	description	path

Value	Column 1	Column 2
-	direction-mask	"000000000001111"
region		
-	anchor	Lat: 41.15315006 Lon: -104.64710095
-	lane-width	50 m
-	directionality	3
-	closed-path	false
-	description	path
-	direction-mask	"000000000001111"
suggested icon		-

The packetID and message count together uniquely identify the TIM. The provided packetID is an example value. For this initial TIM version, the message count is set to 1. Subsequent updates or revocations of this TIM will increment the message count. A depiction of the Geographic Validity Region of the TIM is shown in the figure above. The validity region geofence for this TIM consists of two sequential regions as indicated in the parameters listed above. To get the exact path definition the encoded TIM included below can be decoded. The validity region geofence is defined as a path along the roadway with a 50-meter lane width. Note, the heading direction mask defines valid vehicle headings to provide this alert. In this case a driver alert for this TIM should be displayed while traveling in a northwest direction through the TIM geofence (counterclockwise direction around the test oval). A suggested driver display icon is provided; this is the suggested graphic to display for the driver if the OBU provides such a display.

The following hex string is a signed and encoded version of the initial Variable Speed Limit TIM described above:

```
03810040038081ce001f80ca701575588d442ef002fc6b1b010f775d9b0301c27160d9416752ca37fff93f42
baac21c0a017f98a7c32e5c9334edd3d10356a820f2c7a32f24145a2e6300000000138b06ca0b3a965189c
46000f1087033d5e9817e3a0405d7f4e15f7e8cc0a8a340485040a4b826db525c134d286a091434973fcc5
3e1972e499a76e9e881ab54107963d197920a2d17328000000009c58c3da59d3e13a4e23000788428492
3a0244bdf50e8a25aea85bd128e2c24b895d6e07a821c6c18810c2e000001900430626e22103ddd766c06
00183000251a824822ff40002520c01ff120081010100030180c620fb90caad3b9c508208511422512865ac
bd396921000326e52b7883279c83010180034801010001838183748c51728ff0d88dad3ecd5a87c471e77f
b53eb57db0dad64fe5c85dd5c59e52808045321cb9c97bb27a57de5c5732d970930c24ae1071977839e3e
6bd1f47b151f1b4f9be2fd7c9ad3d3f809dee0fdf6eb6e64bffc059e2c65cadf07ed0b51937c9
```

During the tests, the start time and duration will be configured for the broadcast TIMs to support a series of updates and revocations.

Each deployment will then either deploy the message directly to an RSU in the test environment or provide the message to the deployment agency that controls that RSU for deployment. The deployment agency will also detail whether:

- They sign their TIM messages at the TMC.
- They sign their TIM messages at the RSU (expected way for most testing).
- They sign their TIM messages at the TMC, send to the RSU, RSU validates the signature on the TIM and then strips the certificate and signs with its certificate.

Vehicles with different OBU models will start driving at the top of the oval track from the north most roundabout, traveling counterclockwise around the oval, passing through the Weather Warning and Work Zone TIMs. Observers will note that the Speed Limit TIM should appear on the HMI as the vehicle enters the geofence in the northeast quadrant of the oval track and should note the approximate time and location when the TIM appeared.

The vehicles will turn around through the north most roundabout and drive through the TIM geofence traveling clockwise around the oval. Observers should note that the Variable Speed Limit TIM does not appear on the HMI as the vehicle is traveling in the opposite direction of the defined valid heading mask.

13.3.1.3 Pass/Fail Criteria

- RSUs correctly broadcast the Variable Speed Limit TIM.
- OBUs receive the Variable Speed Limit TIM and display it only in the valid direction and Geographic Validity Region.

13.3.2 Variable Speed Limit TIM Update


13.3.2.1 Test Objective

The objective of the Variable Speed Limit TIM Update test case is for deployments to update their original Variable Speed Limit TIM message and verify that the OBUs update the TIM message that resides in their devices.

13.3.2.2 Test Description

The update to the Variable Speed Limit TIM will change the defined speed limit from 55 mph down to 45 mph. This represents a typical update that might be made in an area where changing conditions warrant a speed limit reduction. The updated TIM will retain the same packetID as the original, but will increment the message count to indicate this updated TIM supersedes the original TIM. In addition to the incremented message count, the ITIS codes will be updated to reflect the speed limit change. The previous version will remain broadcasting to ensure the OBUs are checking the message count and only displaying the latest TIM. These changes are indicated in the TIM parameters in the table below.

Table 8: VSL TIM Update

Value	Column 1	Column 2
msgCnt	2	-
packetID	8D442EF002FC6B1B01	-
dataframe	-	-
-	content	speedLimit
-	itis-codes	268, 12589, 8720
region	-	-
region	-	-
-	-	-
suggested icon		-

The following hex string is a signed and encoded version of the updated Variable Speed Limit TIM described above:

```
03810040038081ce001f80ca702575588d442ef002fc6b1b010f775d9b0301c27160d9416752ca37fff93f42
baac21c0a017f98a7c32e5c9334edd3d10346a820f2c7a32f24145a2e6300000000138b06ca0b3a965189c
46000f1087033d5e9817e3a0405d7f4e15f7e8cc0a8a340485040a4b826db525c134d286a091434973fcc5
3e1972e499a76e9e881a354107963d197920a2d17328000000009c58c3da59d3e13a4e23000788428492
3a0244bdf50e8a25aea85bd128e2c24b895d6e07a821c6c18810c2e000001900430625a22103ddd766c06
00183000251a91999162b0002520c01ff120081010100030180c620fb90caad3b9c508208511422512865a
cbd396921000326e52b7883279c83010180034801010001838183748c51728ff0d88dad3ecd5a87c471e7
7fb53eb57db0dad64fe5c85dd5c59e52808090ceef9121f40e0b80de326440362522d60938bcb749b2f1c13
5a7429633aaa46f71709484567d0e5666bca6c344cf81db5716160f0af0e088a55fab74528639
```

Deployments will update their Speed Limit TIM with this speed limit change and resend that TIM to the test environment RSUs. Vehicles may need to remain running between the original test and this update test to ensure the original TIM remains on the OBU and that the updated TIM supersedes the original version. The vehicles will then travel the same pattern as described in Section 13.2.1.2, however in this case, the displayed message should reflect the updated speed limit. As an additional check, inspection of the OBU logs should show the TIM was updated internally to the latest version.

13.3.2.3 Pass/Fail Criteria

- RSUs correctly broadcast the updated Variable Speed Limit TIM.

-
- OBUs receive the updated Variable Speed Limit TIM and display it only in the valid direction and Geographic Validity Region.
 - OBUs update their internal saved version of the Variable Speed Limit TIM with the updated TIM.

13.4 Work Zone TIM

13.4.1 Work Zone TIM Creation and Delivery

13.4.1.1 Test Objective

The objective of the Work Zone TIM Creation and Delivery test case is for multiple deployments to generate a work zone TIM for work zone warning according to their operational processes, distribute that TIM to an RSU and have multiple different vendor OBUs drive past the RSU, store the TIM and then display the TIM only when it meets the criteria for display. The intent is to demonstrate that the TIM messages generated by each of the participating deployments can be received and displayed with the relevant information by each of the different OBU models.

TIMs for a roadway work zone are typically assembled as a combination of TIMs, each one providing information about different elements of a road construction zone. The TIMs assembled for the Work Zone TIM test include a regulatory reduced speed zone, a lane closure warning, and a construction site location.

13.4.1.2 Test Description

The initial step of this test will be for all participating deployment agencies to generate TIMs for a work zone as described below:





Figure 15 Work Zone TIM location

13.4.1.2.1 Reduced Speed Zone

The first TIM for the work zone defines the reduced regulatory speed limit imposed for the work zone. This TIM includes two data frames, the first contains the area where the new speed limit is in effect and the second is an upstream warning for motorists about the upcoming reduced speed limit.

Table 9: Reduced Speed TIM

Value	Column 1	Column 2
msgCnt	1	-
packetID	8D442EF011020B1C01	-
dataframe	-	-
-	content	speedLimit
-	itis-codes	268, 12589, 8720
region	-	-
-	anchor	Lat: 41.1472587 Lon: -104.6513098
-	lane-width	50 m
-	directionality	3
-	closed-path	false
-	description	path
-	direction-mask	"0111000000000000"
suggested icon		-
dataframe	-	-
-	content	speedLimit
-	itis-codes	268, 12302, 12589, 8720, 13569
region	-	-
-	anchor	Lat: 41.14899435 Lon: -104.6633312
-	lane-width	50 m
-	directionality	3
-	closed-path	false
-	description	path
-	direction-mask	"0011111000000000"
suggested icon		-

The packetID and message count together uniquely identify the TIM. The provided packetID is an example value. For this initial TIM version, the message count is set to 1. Subsequent updates or revocations of this TIM will increment the message count. A depiction of the Geographic Validity Region of the TIM is shown in the figure above. This TIM includes two dataframes, one for the speed limit and the second for the speed reduction warning. Each dataframe contains the ITIS codes and the validity region geofence for their respective messages. Within each region definition, the direction mask defines valid vehicle headings for this alert. For these reduced speed warnings, driver alerts should be displayed while traveling in an easterly direction through the TIM geofence (counterclockwise direction around the test oval). A suggested driver display icon is provided; this is the suggested graphic to display for the driver if the OBU provides such a display.

The following hex string is a signed and encoded version of the Work Zone reduced speed limit TIM described above:


```
03810040038082011a001f8116701575588d442ef011020b1c010f775d9b0b01c2715bde59674a61afff93f
42baac21c0a007f98afb96bf5bf765414f865cb91041e58f465e4828b26700000000138adef2cb3a530d49c
4670001088067d4a3077388e383dc64bda2a9b6897b153ad45c707994a84c3cfc7b41d9bad560dc5757b
86b059ed00064010c189688840f775d9b180e138aefe60b39dda7fffc9fa15d5610e05003fd057dfcb5fadfb
2a0a7c32e5c882965c9d71e5c8820f2c7a32f241459338000000009c577f3059ceed3e4e231f0008458296
9000387625541e0052aa0f3f2a1307d1f57b454868ebda2ab4977b4156d33ded0abe75f55456976fed02b8
46817b1566e42390aa22215540068010c18070c4b4442035013ddd766c0600183000251bd1b9ece01000
2520c01ff120081010100030180c620fb90caad3b9c508208511422512865acbd396921000326e52b78832
79c83010180034801010001838183748c51728ff0d88dad3ecd5a87c471e77fb53eb57db0dad64fe5c85dd
5c59e5280805f6c1e7293fa8efeeb6e9cbaa990b013f400e8f0bf971373f6850c0c3387083ad2c7eb7f2ed29
d923115dcefa4bf07c8752cd77d4ff362bf9b6dd03e76d3397c
```

13.4.1.2.2 Right Lane Closed Ahead

The second TIM for the work zone is a lane closure warning. It provides a warning for oncoming motorists that the right lane is closed ahead of them.

Table 10: Lane Closure TIM

Value	Column 1	Column 2
msgCnt	1	-
packetID	8D442EF0010D5C1C01	-
dataframe	-	-
-	content	workZone
-	itis-codes	8196, 771
region	-	-

Value	Column 1	Column 2
-	anchor	Lat: 41.147205668 Lon: -104.6590462
-	lane-width	50 m
-	directionality	3
-	closed-path	false
-	description	path
-	direction-mask	"0011110000000000"
suggested icon		-

The packetID and message count together uniquely identify the TIM. The provided packetID is an example value. For this initial TIM version, the message count is set to 1. Subsequent updates or revocations of this TIM will increment the message count. A depiction of the Geographic Validity Region of the TIM is shown in the figure above. To get the exact path definition the encoded TIM included below can be decoded. The validity region geofence is defined as a path along the roadway with a 50-meter lane width. Note, the heading direction mask defines valid vehicle headings to provide this alert. In this case a driver alert for this TIM should be displayed while traveling in an eastbound direction through the TIM geofence (counterclockwise direction around the test oval). A suggested driver display icon is provided; this is the suggested graphic to display for the driver if the OBU provides such a display.

The following hex string is a signed and encoded version of the Work Zone lane closure warning TIM described above:

03--
8100400380818d001f8089701575588d442ef0010d5c1c010f775d9b0301c2715bc96740f00ffff93f42baa
c21c0a007f9aa5a73e8e9330eeca821ecd2e44107963d197920a2c99c000000004e2b79b92ce81e0127
118f000422013eed02b3287b42158cabeaa8adacdfda054ac501302a434825f1527ec2390ab37215543e5


d497c1f60e5ed00088801006067bbaecd80600183000251bf4a8a8dc50002520c01ff120081010100030180c620fb90caad3b9c508208511422512865acbd396921000326e52b7883279c83010180034801010001838183748c51728ff0d88dad3ecd5a87c471e77fb53eb57db0dad64fe5c85dd5c59e52808020b4d34048341707c2963bd6f050b20364824bfc4a7487604b52767d954688f8a833c460c2308bd18552c980f5d4935fab93e3905bc2b34afc30307842cb162c

13.4.1.2.3 Work Zone

The third work zone TIM identifies the exact area of the work zone.

Table 11: Work Zone TIM

Value	Column 1	Column 2
msgCnt	1	-
packetID	8D442EF0F00E5C1C01	-
dataframe	-	-
-	content	workZone
-	itis-codes	1025
region	-	-
-	anchor	Lat: 41.1476001 Lon: -104.6494760
-	lane-width	50 m
-	directionality	3
-	closed-path	false
-	description	path
-	direction-mask	"0111000000000000"

Value	Column 1	Column 2
suggested icon		-

The packetID and message count together uniquely identify the TIM. The provided packetID is an example value. For this initial TIM version, the message count is set to 1. Subsequent updates or revocations of this TIM will increment the message count. A depiction of the Geographic Validity Region of the TIM is shown in the figure above. To get the exact path definition the encoded TIM included below can be decoded. The validity region geofence is defined as a path along the roadway with a 50-meter lane width. Note, the heading direction mask defines valid vehicle headings to provide this alert. In this case a driver alert for this TIM should be displayed while traveling in an eastbound direction through the TIM geofence (counterclockwise direction around the test oval). A suggested driver display icon is provided; this is the suggested graphic to display for the driver if the OBU provides such a display.

The following hex string is a signed and encoded version of the Work Zone warning TIM described above:

```
0381004003806e001f6b701575588d442ef0f00e5c1c010f775d9b0301c2715c4911674c9eb7fff93f42baac
21c0a007f91afb96bf5bf7654107963d197920a2ce00000002715c4911674c9eb1388ce00021080993800
0eda72d087d1fa2603c97d1c81f2eac720e36b4bd8004008027bbaecd80600183000251bf4a985e0a00025
20c01ff120081010100030180c620fb90caad3b9c508208511422512865acd396921000326e52b7883279
c83010180034801010001838183748c51728ff0d88dad3ecd5a87c471e77fb53eb57db0dad64fe5c85dd5c
59e528080421ffc5d12daeb410ec5cb5cf2abbe8ae729672e7e0643f00c87b59f198ebd95843ab35ade3d36
ff5035f782e4695367c72863b06b81845a4be13044fb46b892
```

During the tests, the start time and duration will be configured for the broadcast TIMs to support a series of updates and revocations.

Each deployment will then either deploy the message directly to an RSU in the test environment or provide the message to the deployment agency that controls that RSU for deployment. The deployment agency will also detail whether:

- They sign their TIM messages at the TMC.
- They sign their TIM messages at the RSU (expected way for most testing).

-
- They sign their TIM messages at the TMC, send to the RSU, RSU validates the signature on the TIM and then strips the certificate and signs with its certificate.

Vehicles with different OBU models will start driving at the top of the oval track from the north most roundabout, traveling counterclockwise around the oval, passing through the Weather Warning TIM. Observers should note the approximate time and location for each of the work zone related TIMs that appear on the HMI as the vehicle traverses the full work zone section.

The vehicles will continue around the oval to complete the following TIM test then turn around through the north most roundabout and drive through the Work Zone TIM geofence traveling clockwise around the oval (after first passing through Variable Speed Limit). Observers should note that none of the work zone related TIMs should appear on the HMI as the vehicle is traveling in the opposite direction of the defined valid heading masks.

13.4.1.3 Pass/Fail Criteria

- RSUs correctly broadcast the Work Zone TIMs.
- OBUs receive the Work Zone TIMs and display them only in their valid direction and Geographic Validity Region.

13.5 End of Ramp Deceleration Warning (ERDW) TIM

13.5.1 ERDW TIM Creation and Delivery

For this interoperability testing, the ERDW lane geometry of the THEA REL is adapted to the red circled location of the Wyoming test site.



Figure 16: Wyoming ERDW Lane Geometry Adaptation

Short queue operation on the Wyoming track is shown in Figure 17. Queue length is set manually, and the ACM test procedure is repeated for short queue.




Figure 17: Wyoming ERDW Lane Geometry Adaptation for Short Queue

Long queue operation on the Wyoming track is shown in Figure 18. Queue length is set manually, and the ACM test procedure is repeated for long queue. Once long and short queues are set and verified manually, the camera is enabled to sense stopped cars within its field of view that automatically triggers long queue.





Figure 18: Wyoming ERDW Lane Geometry Adaptation for Long Queue


13.5.1.1 Test Objective

The objective of the ERDW TIM Creation and Delivery test case is for multiple deployments to generate a ERDW TIM for vehicles approaching a variable length queue extending from an imaginary signalized intersection at the end of an expressway exit ramp. Multiple different vendor OBUs/ASDs drive past the RSU, store the TIM and then display the TIM only when it meets the criteria for display. The intent is to demonstrate that the TIM messages generated by each of the participating deployments can be received and displayed with the relevant information by each of the different OBU/ASD models.

Table 12: ERDW Short Queue TIM

Value	Column 1	Column 2
msgCnt	1	-
packetID	0000000000326E0C0D	-
dataframe	-	-
-	msgId roadSignID.mutcdCode	regulatory
-	content	speedLimit
-	itis-codes	268, 12584, 8720
region	-	-
-	anchor	Lat: 41.1498618 Lon: -104.6574771
-	lane-width	1500 cm
-	directionality	3
-	closed-path	false
-	description	path
-	direction-mask	"1100001111000011"


Value	Column 1	Column 2
suggested icon		-
dataframe	-	-
-	msgId roadSignID.mutcdCode	warning
-	content	advisory
-	itis-codes	268, 12574, 8720
region	-	-
-	anchor	Lat 41.1490990 Lon: -104.6581285
-	lane-width	1500 cm
-	directionality	3
-	closed-path	false
-	description	path
-	direction-mask	"1110000011100000"
suggested icon		-


Value	Column 1	Column 2
dataframe	-	-
-	msgId roadSignID.mutcdCode	warning
-	content	advisory
-	itis-code	268, 12564, 8720
region	-	-
-	anchor	Lat: 41.1481902 Lon: -104.6586837
-	lane-width	1500 cm
-	directionality	both
-	closed-path	false
-	description	path
-	direction-mask	"1100000111000001"
suggested icon		-


The following hex string of Short Queue unsigned ERDW TIM described above:

```
001f810f201000000000326e0c0d480729c57405c59d05854200183824fd0b93abf4030007e538ae80b8b
3a0b0a840002ee6c1c10020a8cf8885547c72aa60dc8027d85737fc63a27e14d5873f6c04fb00001004306
228221040394e2bc3ae2ce841da56bee0e027e85c9dbfa018003f29c57875c59d083b4ad7c17737070000
81877544b4c74da5e1cb99604fb0b19b994000080218311e1108202ca715f0bd16742da6080061e18bf42e
4f17d00c001f94e2be17a2ce85b4c10000bb9b0f0c0183a76e0407953f5c33018e1140a0a1e54fd443a9867
40740cca52e89fcf8027d8513d896290eebf5438fa302590b838f2781ac87d96fd3ebf02590b80062b012c85
416e4703590fb000c802183128110800
```

Table 13: ERDW Long Queue TIM

Value	Column 1	Column 2
msgCnt	1	-
packetID	000000000323928D8	-
dataframe	-	-
-	msgId roadSignID.mutcdCode	regulatory
-	content	speedLimit
-	itis-codes	268, 12584, 8720
region	-	-
-	anchor	Lat: 41.1521866 Lon: -104.6558164
-	lane-width	1600 cm
-	directionality	3
-	closed-path	false
-	description	path
-	direction-mask	"1100001111000001"
suggested icon		-
dataframe	-	-

Value	Column 1	Column 2
-	msgld roadSignID.mutcdCode	warning
-	content	advisory
-	itis-code	268, 12574, 8720
region	-	-
-	anchor	Lat: 41.1513334 Lon: -104.6562146
-	lane-width	1500 cm
-	directionality	3
-	closed-path	false
-	description	path
-	direction-mask	"1100000111000001"
suggested icon		-
dataframe	-	-
-	msgld roadSignID.mutcdCode	warning
-	content	advisory
-	itis-codes	268, 12564, 8720
region	-	-
-	anchor	Lat: 41.1503376 Lon: -104.6570543

Value	Column 1	Column 2
-	lane-width	1600 cm
-	directionality	both
-	closed-path	false
-	description	path
-	direction-mask	"1110000011100000"
suggested icon		-

The following hex string is a Long Queue unsigned ERDW TIM described above:

```
001f80f5201000000000323928d8480729c57e82059d0d7a01fedc1c04fd0b9337f4018007e538afd040b3
a1af403fd82ee6e0e00018aaeb561b2e17475205050ac533f854678f00a1f500000200860c450442080729
c5835ec59d1193aad7d83824fd0b9343f4030007e538b06bd8b3a232755af82ee6c1c10028e8199061cddb
04cb98a658009f614e17f18a3e3508305f508244fb4000080218311e1108202ca7161e2516744e15880060
e08bf42e4d87d00c001f94e2c3c4a2ce89c2b1000c81b070400e28b4f5c1438f27aa05f1b409f613faeb7a5
e9f4904fd08ff4e2c8982f8c413f40c44d42896b9f027d80064010c1894088400
```

13.5.1.2 Test Description

The initial step of this test will be for an RSU to transmit an ERDW TIM with the parameters of Figure 17 and Figure 18. Marker cones are placed at the roadside at the end of queue location, plus at each trigger point shown in Figure 17 and Figure 18.

Vehicles with different OBU/ASD models will start driving at the top of the oval track from the Laramie County Planning Department building, traveling counterclockwise around the oval. Observers will note that the ERDW TIM should appear on the HMI as the vehicle enters the geofence in the upper left

quadrant of the oval track and should note the approximate time and location when the TIM appeared as compared to the cones placed at the roadside. The test is repeated for both long queue and short queue lengths as well as traveling at speeds above and below the speed advice.

13.5.1.3 Pass/Fail Criteria

- RSUs correctly broadcast the ERDW TIM
- OBUs/ASDs receive the ERDW TIM and display it correctly between trigger points only when exceeding the deceleration speed advice.

13.6 Pedestrian Crash Warning (PCW) TIM

13.6.1 PCW TIM Creation and Delivery

The objective of the PCW TIM Creation and Delivery test case is for THEA to generate a Crosswalk TIM for crosswalk warning according to their operational processes, distribute that TIM to an RSU and have multiple different vendor OBUs drive past the RSU, store the TIM and then display the TIM only when it meets the criteria for display. The intent is to demonstrate that the TIM messages generated by each of the participating deployments can be received and displayed with the relevant information by each of the different OBU models.

PCW TIM testing will utilize the intersection of Field Station Way and Archer Parkway, indicated by the circled location of the Wyoming Archer Track test site in Figure 19. Figure 20 describes the base configuration for this test and the direction of vehicle flow during testing.



Figure 19: Wyoming PCW Lane Geometry Adaptation





Figure 20: WY PCW Test Site Configuration

RSU and sensor are installed at the Field Station Way-Archer Parkway intersection, with vehicle approaches and pedestrian approaches matching Figure 20, with the crosswalk marked by four cones, and an installed crosswalk sign. The RSU sends TIM for the MUTCD crosswalk sign continually. Additionally, the RSU can transmit PSMs for pedestrians within the sensor field of view and a PCW TIM when a vehicle is on a collision path and is capable of activating the Rectangular Rapid Flashing Beacon (RRFB) when the crosswalk is occupied. These additional functionalities are excluded from this interoperability test.

13.6.1.1 Test Objectives

The objective of this test case is to verify the Crosswalk TIM in vehicle when approaching the crosswalk for different OBU/ASD models and different directions.

Table 14: PCW TIM

Value	Column 1	Column 2
msgCnt	1	-
packetID	00000000032AC54B2	-
dataframe	-	-
-	msgld roadSignID.mutcdCode	warning
-	content	advisory
-	itis-codes	9486, 13585
region	-	-
-	anchor	Lat: 41.1495865 Lon: -104.6577401
-	lane-width	366 cm
-	directionality	both
-	closed-path	true
-	description	path
-	direction-mask	"1111111111111111"
suggested icon		-

The following hex string is a signed and encoded version of PCW TIM described above:

001f7920100000000032ac54b2080729c57ad7259d0a20c2001ffe4fd0b9501f4028007e538af5ae4b3a1441840000b77ffff00695e05a917054c1896ccb49630027d97be0f9401414bc00afe009f619fa447e17a67f01d60ac1da09585a06ef22a3334521d870ca0cbc6148104ee470f35bfdc0000112870d4440

13.6.1.2 Test Description

Test sequences are conducted on the site of Figure 20. For each test sequence, display of crosswalk TIM is verified for each vehicle approach.

13.6.1.3 Pass/Fail Criteria

- RSUs correctly broadcast the Crosswalk TIM
- OBUs/ASDs receive the Crosswalk TIM and display it correctly on each approach.

13.7 Edge Case TIMs

The Edge Case TIM scenarios originated from collaborative conversations between participants during the first three days of testing. The edge cases are less about determining whether a test was successful and more about learning how TIMs and the equipment respond during uncommon scenarios.

13.7.1 Message Count Turn-Over

13.7.1.1 Test Objective

The objective of this test is to understand what happens when the message count turns over from the final count number, 127, to the first message count number, 0. Each time a new TIM is created the message count increments by one up to 127, so this test is to understand what happens for the message following number 127.

13.7.1.2 Test Description

A Weather Warning TIM is created with the message count set to 127. The TIM is then deployed to the RSU.

Vehicles with different OBU models will start driving at the top of the oval track from the north most roundabout, traveling counterclockwise around the oval. Observers will note that the Weather Warning TIM appears on the HMI as the vehicle enters the geofence in the northwest quadrant of the oval track and should note the approximate time and location when the TIM appeared. Observers should also note any unexpected results from this edge case.

An updated version of the Weather Warning TIM is created, which will increment the message count by one, now having a message count of 0. The TIM is then deployed to the RSU.

Vehicles will drive the track again as before, noting the Weather Warning TIM as it appears. Observers should also note any unexpected results from this edge case.

13.7.1.3 Pass/Fail Criteria

- RSUs correctly broadcast the Weather Warning TIM.
- OBUs receive the Weather Warning TIM and display it only in the valid direction and Geographic Validity Region.

13.7.2 TIM Update to a Different Message Type with Same ID

13.7.2.1 Test Objective

The objective of this test is to test and understand what happens when a Weather Warning TIM is updated to a Work Zone Warning TIM, but the TIM ID is not updated or changed. The goal is to observe whether the Work Zone TIM is displayed when received by OBUs or whether OBUs still show the original Weather Warning TIM. The type of TIM message is not important for this test. The importance is that the TIM type is changed to a different type without updating the TIM ID.

13.7.2.2 Test Description

A deployed Weather Warning TIM is changed to a Work Zone Warning TIM without changing the TIM ID. The message is then deployed to the RSU.

Vehicles with different OBU models will start driving at the top of the oval track from the north most roundabout, traveling counterclockwise around the oval to the Weather Warning TIM geofence, which is now a Work Zone TIM. Observers will note which type of TIM appears on the HMI (expected to be a Work Zone message but could still show a Weather Warning message) as the vehicle enters the geofence in the northwest quadrant of the oval track and should note the approximate time and location when the TIM appeared. Observers should also note any unexpected results from this edge case.

13.7.2.3 Pass/Fail Criteria

- RSUs correctly broadcast the Work Zone Warning TIM.
- OBUs receive the Work Zone Warning TIM and display it only in the valid direction and Geographic Validity Region.

13.7.3 Message Priority

13.7.3.1 Test Objective

The objective of this test is to test and understand what happens with two messages are sent with the same priority and then with different priorities. Checking the OBU logs is more important for this edge case to understand which version of the TIM is received and displayed since both versions that are deployed are Variable Speed Limit TIMs.

13.7.3.2 Test Description

Two Variable Speed Limit TIMs were deployed at the same time in the same geofence. Each TIM is identified with two versions, V1 and V2. In the first iteration, both versions are assigned a priority of 0. The messages are then deployed.

Vehicles with different OBU models will start driving at the top of the oval track from the north most roundabout, traveling counterclockwise around the oval until reaching and driving through the Variable Speed Limit TIM geofence. Observers will note that the Variable Speed Limit TIM appears on the HMI as the vehicle enters the geofence and should note the approximate time and location when the TIM appeared. Observers should also note any unexpected results from this edge case.

The V2 TIM is then updated to V3 with the priority set to 7. There are now two Variable Speed Limit TIMs with different priorities, V1 with a priority of 0 and V3 with a priority of 7. The V3 TIM is then deployed.

Vehicles with different OBU models will start driving at the top of the oval track from the north most roundabout, traveling counterclockwise around the oval until reaching and driving through the Variable Speed Limit TIM geofence. Observers will note that the Variable Speed Limit TIM appears on the HMI as the vehicle enters the geofence and should note the approximate time and location when the TIM appeared. Observers should also note any unexpected results from this edge case.

13.7.3.3 Pass/Fail Criteria

- RSUs correctly broadcast the Variable Speed Limit TIM.
- OBUs receive the Variable Speed Limit TIM and display it only in the valid direction and Geographic Validity Region.

13.7.4 Atypical Speed Limit Value

13.7.4.1 Test Objective

The objective of this test is to test and understand how OBUs react to atypical speed limit value messages. Atypical speed limit values, such as 42 mph, do not have regulatory speed limit signs, so the objective was to test if OBUs display these speeds and what message and icons are displayed if so.

13.7.4.2 Test Description

Two Variable Speed Limit TIMs were created using atypical speed limit values. One TIM was created to share a speed limit of 30 mph. The second TIM was created for 42 mph. The TIMs were created and deployed using the same directions as section 13.2.1.

13.8 Test Case Prioritization

Due to time constraints, it may not be possible to conduct all of the test cases listed above. Table 7 lists the test cases in order of priority. The execution of test cases will focus on the higher priority test cases first and accomplish the others as time permits.

Table 15. Test Case Prioritization

Priority	Test Case
1	Weather Warning TIM
2	Variable Speed Limit TIM
3	Work Zone TIM
4	End of Ramp Deceleration Warning TIM
5	Pedestrian Crash Warning TIM
6	Edge Case TIMs

14 Test Procedures

14.1 Baseline OBU Data Collection

The path for the Baseline OBU Data Collection Tool is depicted in the figure below.




Figure 11. Baseline OBU Data Collection Path 1

Table 16 includes the Test Procedures for the Baseline OBU Data Collection

Table 16. Baseline OBU Data Collection Test Procedures Path

ID	Step	Action	Expected Result	Pass/Investigate/Fail
1.	Verify Readiness	WYDOT OBU is installed in Vehicle and operating	-	Pass/Fail
2.	Verify Readiness	CDOT OBU is installed in Vehicle and operating	-	Pass/Fail
3.	Verify Readiness	GDOT OBU is installed and operating	-	Pass/Fail

U.S. Department of Transportation
 Office of the Assistant Secretary for Research and Technology
 Intelligent Transportation Systems Joint Program Office

ID	Step	Action	Expected Result	Pass/Investigate/ Fail
4.	Verify Readiness	UDOT OBU is installed and operating	-	Pass/Fail
5.	Verify Readiness	THEA OBU is installed and operating	-	Pass/Fail
6.	Verify Readiness	DENSO OBU is installed and operating	-	Pass/Fail
7.	Test Vehicle	Travel to the beginning of the Test path (Point A) as shown in Figure 11	-	-
8.	Test Vehicle	Travel along Prairie Center Circle counterclockwise	-	-
9.	Test Vehicle	Continue straight until reaching Point B in Figure 11	-	-
10.	Test Vehicle	Repeat Steps 7 - 9 three more times	-	-
11.	Verify Data Collection	Verify that data was collected by each of the OBUs installed on the Test Vehicle	-	Pass/Fail

14.1.1 Noise Baseline Measurements

These test procedures will be performed each morning before testing subsequent TIMs.

Table 17: Noise Baseline Measurements Test Procedures

ID	Step	Action	Expected Result	Pass/Investigate/ Fail
1.	Verify TIM readiness	Verify that start time and duration has been configured to broadcast the TIMs	-	-
2.	Deploy TIM	The first participant will either deploy the message directly to an RSU in the test environment or provide the message to the deployment agency that controls that RSU for deployment	-	-
3.	Sign TIM	The deployment agency will sign the TIM using their protocol	RSUs correctly broadcast the Weather Warning TIM	Pass/Fail
4.	Setup devices in vehicle	Equip vehicle with an RSU and sniffer to passively receive distributed TIM messages	-	-
5.	Establish RDP Connection	Establish an RDP connection through a cellular modem for the control of additional devices in the vehicle	-	Pass/Fail
6.	Begin driving	The vehicle will start driving at the top of the oval track from the north most roundabout, traveling counterclockwise around the oval	-	-
7.	Continue driving	The vehicle will complete a full loop of the test track then head south on Archer Parkway to pass through all five measurement locations	-	-
8.	Return to Laramie County Office	The vehicles will return to the office to download data	-	-
9.	Process pcap files	If time permits, process pcap files from raw files for each device	-	-

14.2 Weather Warning TIM

Table 18. Weather Warning TIM Test Procedures

ID	Step	Action	Expected Result	Pass/Investigate/ Fail
1.	Verify TIM readiness	Verify that start time and duration has been configured to broadcast the TIMs	-	-
2.	Deploy TIM	The first participant will either deploy the message directly to an RSU in the test environment or provide the message to the deployment agency that controls that RSU for deployment	-	-
3.	Sign TIM	The deployment agency will sign the TIM using their protocol	RSUs correctly broadcast the Weather Warning TIM	Pass/Fail
4.	Begin driving	The participant vehicles will start driving at the top of the oval track from the north most roundabout, traveling counterclockwise around the oval	-	-
5.	Observe TIM	Observers will note the Weather Warning TIM as it appears on the HMI as the vehicle enters the geofence by taking a picture or screenshot of the TIM image	OBU's receive the Weather Warning TIM and display the correct TIM image	Pass/Fail
6.	Note TIM time and location	Observers will note the approximate time and location when the TIM appears	-	-
7.	Continue driving to next TIM	The vehicles will proceed on the oval track through the next two TIM geofences (Work Zone and Variable Speed Limit)	-	-
8.	Vehicle turn around and drive clockwise	The vehicles will turn around through the north most roundabout and drive through the two TIM geofences traveling clockwise around the oval	-	-
9.	Observe TIM on secondary pass through geofence	Observers will note that the Weather Warning TIM as it appears on the HMI as the vehicle enters the geofence from the west side by taking a picture or screenshot of the TIM image	RSUs correctly broadcast the Weather Warning TIM	Pass/Fail
10.	Note time and location	Observers will note the approximate time and location when the TIM appears on the secondary pass through the geofence	-	-
11.	Return to Laramie County Office	The vehicles will return to the office to download data and prepare for the next portion of the test	-	-

ID	Step	Action	Expected Result	Pass/Investigate/Fail
12.	Increment original TIM	The participants will increment the newly generated TIM to change its validity time so that it becomes invalid within 5 minutes of the current time	-	-
13.	Update TIM to revoke	Participant will update the TIM with the validity time change	-	-
14.	Resend TIM	Participant will resend the TIM to the RSUs	-	-
15.	<i>Note</i>	<i>Vehicles may need to remain running to ensure the original TIM remains on the OBU and that the revocation TIM supersedes the original version</i>	-	-
16.	Begin driving	The vehicles will drive the same path as in Step 4	-	-
17.	Observe no TIM	The observer should note no TIM while passing through the geofence	OBU's do not receive a Variable Speed Limit TIM	Pass/Fail
18.	Repeat	Repeat Steps 4-17 for the following participant	-	-

14.2.1 Test Combinations Matrix

Table 19: Test Combinations Matrix

Weather Warning TIM	Participant RSUs	WYDOT (ISS)	WYDOT (Autocrypt)	CDOT	GDOT	UDOT	THEA
Participant OBU's	-	-	-	-	-	-	-
WYDOT (ISS)	-	-	-	-	-	-	-
WYDOT (Autocrypt)	-	-	-	-	-	-	-
CDOT	-	-	-	-	-	-	-
GDOT	-	-	-	-	-	-	-
UDOT	-	-	-	-	-	-	-
THEA	-	-	-	-	-	-	-
DENSO	-	-	-	-	-	-	-

14.3 Variable Speed Limit TIM

Table 20. Incident TIM Test Procedures

ID	Step	Action	Expected Result	Pass/Investigate/Fail
1.	Verify TIM readiness	Verify that start time and duration has been configured to broadcast the TIMs	-	-
2.	Deploy TIM	The first participant will either deploy the message directly to an RSU in the test environment or provide the message to the deployment agency that controls that RSU for deployment	-	-
3.	Sign TIM	The deployment agency will sign the TIM using their protocol	RSUs correctly broadcast the Variable Speed Limit TIM	Pass/Fail
4.	Begin driving	The participant vehicles will start driving at the top of the oval track from the north most roundabout, traveling counterclockwise around the oval	-	-
5.	Observe TIM	After passing through the Work Zone TIM, observers will note the Variable Speed Limit TIM as it appears on the HMI as the vehicle enters the geofence by taking a picture or screenshot of the TIM image	OBU receive the Variable Speed Limit TIM and display the correct TIM image	Pass/Fail
6.	Note TIM time and location	Observers will note the approximate time and location when the TIM appears	-	-
7.	Vehicle turn around and drive clockwise	The vehicle will turn around through the north most roundabout and drive through the VSL TIM geofence, now traveling clockwise	-	-
8.	Observe no TIM when passing through geofence in opposite direction	Observers will note that the Variable Speed Limit TIM does not appear on the HMI as the vehicle enters the geofence from the opposite direction	OBU do not receive a Variable Speed Limit TIM	Pass/Fail
9.	Return to Laramie County Office	The vehicles will continue around the oval loop, returning to the office to download data and prepare for the next portion of the test	-	-
10.	Update original TIM	The participant will change the speed limit from 55 mph to 45 mph	-	-
11.	Resend TIM	Participant will resend the TIM to the RSUs	-	-

ID	Step	Action	Expected Result	Pass/Investigate/Fail
12.	Note	<i>Vehicles may need to remain running to ensure the original TIM remains on the OBU and that the revocation TIM supersedes the original version</i>	-	-
13.	Begin driving	The vehicles will drive the same path as in Step 4	-	-
14.	Observe updated TIM	After passing through the Work Zone TIM, observers will note the TIM with new speed limit and take a picture or screenshot of the TIM image	OBU's receive the updated Variable Speed Limit TIM and display the correct TIM image	Pass/Fail
15.	Note TIM time and location	Observer will note the approximate time and location when the TIM appears	-	-
16.	Repeat	Repeat Steps 4-15 for the following participants	-	-

14.3.1 Test Combinations Matrix

Table 21: Test Combinations Matrix

Weather Warning TIM	Participant RSUs	WYDOT (ISS)	WYDOT (Autocrypt)	CDOT	GDOT	UDOT	THEA
Participant OBU's	-	-	-	-	-	-	-
WYDOT (ISS)	-	-	-	-	-	-	-
WYDOT (Autocrypt)	-	-	-	-	-	-	-
CDOT	-	-	-	-	-	-	-
GDOT	-	-	-	-	-	-	-
UDOT	-	-	-	-	-	-	-
THEA	-	-	-	-	-	-	-
DENSO	-	-	-	-	-	-	-

14.4 Work Zone TIM

Table 22. Work Zone TIM Test Procedures

ID	Step	Action	Expected Result	Pass/Investigate/Fail
1.	Verify TIM readiness	Verify that start time and duration has been configured to broadcast the TIMs	-	-
2.	Deploy TIM	The first participant will either deploy the message directly to an RSU in the test environment or provide the message to the deployment agency that controls that RSU for deployment	-	-
3.	Sign TIM	The deployment agency will sign the TIM using their protocol	RSUs correctly broadcast the Weather Warning TIM	-
4.	Begin driving	The participant vehicles will start driving at the top of the oval track from the north most roundabout, traveling counterclockwise around the oval	-	-
5.	Observe Reduced Speed Zone TIM	After passing through the Weather Warning TIM, observers will note that the Reduced Speed Zone TIM as it appears on the HMI as the vehicle enters the geofence by taking a picture or screenshot of the warning image	OBU's receive the Reduced Speed Zone TIM and display the correct TIM image	Pass/Fail
6.	Note TIM time and location	Observers will note the approximate time and location when the TIM appears	-	-
7.	Observe Right Lane Closed Ahead TIM	Observers will note the Right Lane Closed Ahead TIM as it appears on the HMI as the vehicle enters the geofence by taking a picture or screenshot of the warning image	OBU's receive the Right Lane Closed Ahead TIM and display the correct TIM image	Pass/Fail
8.	Note TIM time and location	Observers will note the approximate time and location when the TIM appears	-	-
9.	Observe Speed Limit TIM	Observers will note the Speed Limit TIM as it appears on the HMI as the vehicle enters the geofence by taking a picture or screenshot of the warning image	OBU's receive the Speed Limit TIM and display the correct TIM image	Pass/Fail
10.	Note TIM time and location	Observers will note the approximate time and location when the TIM appears	-	-
11.	Observe Work Zone TIM	Observers will note the Work Zone TIM as it appears on the HMI as the vehicle enters the geofence by taking a picture or screenshot of the warning image	OBU's receive the Work Zone TIM and display the correct TIM image	Pass/Fail
12.	Note TIM time and location	Observers will note the approximate time and location when the TIM appears	-	-

ID	Step	Action	Expected Result	Pass/Investigate/ Fail
13.	Vehicle turn around and drive clockwise	The vehicles will turn around through the north most roundabout and drive through the TIM geofence traveling clockwise around the oval	-	-
14.	Observe no TIM when passing through geofence in opposite direction	Observers will note that the sequence of three Work Zone related TIMs do not appear on the HMI as the vehicle enters the geofence from the opposite direction	OBU's do not receive any of the Work Zone TIMs	Pass/Fail
15.	Return to Laramie County Office	The vehicles will continue around the oval loop, returning to the office to download data and prepare for the next test	-	-
16.	Repeat	Repeat Steps 4-13 for the following participants	-	

14.4.1 Test Combinations Matrix

Table 23: Test Combinations Matrix

Weather Warning TIM	Participant RSUs	WYDOT (ISS)	WYDOT (Autocrypt)	CDOT	GDOT	UDOT	THEA
Participant OBU's	-	-	-	-	-	-	-
WYDOT (ISS)	-	-	-	-	-	-	-
WYDOT (Autocrypt)	-	-	-	-	-	-	-
CDOT	-	-	-	-	-	-	-
GDOT	-	-	-	-	-	-	-
UDOT	-	-	-	-	-	-	-
THEA	-	-	-	-	-	-	-
DENSO	-	-	-	-	-	-	-

14.5 End of Ramp Crash Warning (ERDW) TIM

Table 24: End of Ramp Crash Warning Test Procedures

ID	Step	Action	Expected Result	Pass/Investigate/Fail
1.	THEA Setup	THEA to work with onsite staff to setup the RSU and camera in the necessary locations	-	-
2.	Verify TIM Readiness for Short Queue	Verify that start time and duration has been configured to broadcast the TIMs	-	-
3.	Deploy TIM	THEA will deploy the message directly to the RSU in the test environment	-	-
4.	Sign TIM	The deployment agency will sign the TIM using their protocol	RSUs correctly broadcast the ERDW TIM	-
5.	Place Marker Cones	Marker cones will be placed at the roadside at the end of queue location, plus at each trigger point	-	-
6.	Begin driving	The first participant vehicle will start driving at the top of the oval track, following the posted speed limit, from the Laramie County Planning Department building, traveling south on Archer Pkwy until they reach Prairie Center Cir	-	-
7.	Observe 40 MPH Speed Limit TIM	Observers will note the 40 MPH Speed Limit TIM as it appears on the HMI by taking a picture or screenshot	OBU receive the 40 MPH Speed Limit TIM and display the correct TIM image	Pass/Fail
8.	Note TIM time and location	Observer will note the approximate time and locations when each TIM appears	-	-
9.	Observe Reduce Speed TIM	Observers will note the Reduce Speed to 30 MPH TIM as it appears on the HMI by taking a picture or screenshot	OBU receive the Reduce Speed to 30 MPH TIM and display the correct TIM image	Pass/Fail
10.	Note TIM time and location	Observer will note the approximate time and locations when each TIM appears	-	-
11.	Observe Reduce Speed TIM	Observers will note the Reduce Speed to 20 MPH TIM as it appears on the HMI by taking a picture or screenshot	OBU receive the Reduce Speed to 20 MPH TIM and display the correct TIM image	Pass/Fail
12.	Note TIM time and location	Observer will note the approximate time and locations when each TIM appears	-	-

ID	Step	Action	Expected Result	Pass/Investigate/ Fail
13.	Stop at end of road	The vehicle will come to a stop at the end of Archer Parkway and Prairie Center Cir		
14.	Vehicle returns to Planning Department	Vehicle will take a right on to Prairie Center Cir when reaching the end of Archer Pkwy. Vehicles will travel clockwise returning to Laramie County Planning Department	-	-
15.	Each participant repeats	Each participant repeats Steps 6 - 14	-	-
16.	Set up RSU for Long Queue	THEA will update the ERDW TIM to a Long Queue and park a car so that it is in view of the camera to initiate a long queue scenario	-	-
17.	Move marker cones	Marker cones will be moved to mark the end of the long queue and at each, new trigger point	-	-
18.	Begin driving	The first participant vehicle will start driving at the top of the oval track, following the posted speed limit, from the Laramie County Planning Department building, traveling south on Archer Pkwy until they reach Prairie Center Cir	-	-
19.	Observe 40 MPH Speed Limit TIM	Observers will note the 40 MPH Speed Limit TIM as it appears on the HMI by taking a picture or screenshot	OBU's receive the 40 MPH Speed Limit TIM and display the correct TIM image	Pass/Fail
20.	Note TIM time and location	Observer will note the approximate time and locations when each TIM appears	-	-
21.	Observe Reduce Speed TIM	Observers will note the Reduce Speed to 30 MPH TIM as it appears on the HMI by taking a picture or screenshot	OBU's receive the Reduce Speed to 30 MPH TIM and display the correct TIM image	Pass/Fail
22.	Note TIM time and location	Observer will note the approximate time and locations when each TIM appears	-	-
23.	Observe Reduce Speed TIM	Observers will note the Reduce Speed to 20 MPH TIM as it appears on the HMI by taking a picture or screenshot	OBU's receive the Reduce Speed to 20 MPH TIM and display the correct TIM image	Pass/Fail
24.	Note TIM time and location	Observer will note the approximate time and locations when each TIM appears	-	-
25.	Vehicle returns to Planning Department	The vehicle will make a right turn on Field Station Way followed by a right turn on Prairie Center Cir returning to Laramie County Planning Department	-	-
26.	Each participant repeats	Each participant repeats Steps 18 - 25	-	-

14.5.1 Test Combinations Matrix

Table 25: Test Combinations Matrix

ERDW TIM	Participant RSUs	WYDOT (ISS)	WYDOT (Autocrypt)	CDOT	GDOT	UDOT	THEA
Participant OBUs	-	-	-	-	-	-	-
WYDOT (ISS)	-	-	-	-	-	-	-
WYDOT (Autocrypt)	-	-	-	-	-	-	-
CDOT	-	-	-	-	-	-	-
GDOT	-	-	-	-	-	-	-
UDOT	-	-	-	-	-	-	-
THEA	-	-	-	-	-	-	-
Denso	-	-	-	-	-	-	-

14.6 Pedestrian Crash Warning (PCW) TIM

Table 26: Pedestrian Crash Warning Test Procedures

ID	Step	Action	Expected Result	Pass/Investigate/Fail
1.	Verify TIM Readiness	Verify that start time and duration has been configured to broadcast the TIMs	-	-
2.	Deploy TIM	THEA Crosswalk TIM will be deployed directly to an RSU in the test environment or provide the message to the deployment agency that controls that RSU for deployment	-	-
3.	Sign TIM	The deployment agency will sign the TIM using their protocol	RSUs correctly broadcast the PCW TIM	-
4.	Place Crosswalk Marker Cones	Two marker cones will be placed on both sides of Archer Pkwy on the NE section of the Archer Pkwy-Field Station Way intersection designating a pedestrian crosswalk	-	-
5.	Place Crosswalk Sign	A crosswalk sign will be placed prior to the marker cones on the eastern side of Archer Pkwy, facing northbound traffic	-	-
6.	Begin Driving	The first participant vehicle will start driving northbound along Archer Pkwy towards the Archer Pkwy-Field Station Way intersection. The vehicle should maintain a speed no greater than 10 mph through the intersection	-	-
7.	Observe Crosswalk TIM	Observers will note the Crosswalk TIM as it appears on the HMI as the vehicle approaches the intersection	OBU's receive the TIM and display it correctly in the Geographic Validity Region	Pass/Fail
8.	Continue Driving	The first participant vehicle will leave the area and the second participant vehicle will start driving southbound along Archer Pkwy towards the Archer Pkwy- Field Station Way intersection. The vehicle should maintain a speed no greater than 10 mph through the intersection	-	-
9.	Observe Crosswalk TIM	Observers will note the Crosswalk TIM as it appears on the HMI as the vehicle approaches the intersection	OBU's receive the TIM and display it correctly in the Geographic Validity Region	Pass/Fail
10.	Continue Driving	The second participant vehicle will leave the area and the third participant vehicle will start driving southbound on Archer Pkwy towards the Archer Pkwy-Field Station Way intersection	-	-
11.	Repeat	Each participant repeats Steps 6-10	-	-

14.6.1 Test Combinations Matrix

Table 27: Test Combinations Matrix

Weather Warning TIM	Participant RSUs	WYDOT (ISS)	WYDOT (Autocrypt)	CDOT	GDOT	UDOT	THEA
Participant OBUs	-	-	-	-	-	-	-
WYDOT (ISS)	-	-	-	-	-	-	-
WYDOT (Autocrypt)	-	-	-	-	-	-	-
CDOT	-	-	-	-	-	-	-
GDOT	-	-	-	-	-	-	-
UDOT	-	-	-	-	-	-	-
THEA	-	-	-	-	-	-	-
Denso	-	-	-	-	-	-	-

14.7 Edge Case: Message Count Turn-Over

Table 28: Message Count Turn-Over Test Procedures

ID	Step	Action	Expected Result	Pass/Investigate/Fail
1.	Create TIM	Create a Weather Warning TIM and set the message count to 127	-	-
2.	Verify TIM readiness	Verify that start time and duration has been configured to broadcast the TIMs	-	-
3.	Deploy TIM	Deploy the Weather Warning TIM to the RSU	-	-
4.	Sign TIM	The deployment agency will sign the TIM using their protocol	RSUs correctly broadcast the Weather Warning TIM	Pass/Fail
5.	Begin driving	The participant vehicles will start driving at the top of the oval track from the north most roundabout, traveling counterclockwise around the oval	-	-
6.	Observe TIM	Observers will note the Weather Warning TIM as it appears on the HMI as the vehicle enters the geofence by taking a picture or screenshot of the TIM image	OBU's receive the Weather Warning TIM and display the correct TIM image	Pass/Fail
7.	Note TIM time and location	Observers will note the approximate time and location when the TIM appears	-	-
8.	Return to Laramie County Office	The vehicles will return to the office to download data and prepare for the next portion of the test	-	-
9.	Increment original TIM	The TIM is incremented so that the message count is now 0	-	-
10.	<i>Note</i>	<i>Vehicles may need to remain running to ensure the original TIM remains on the OBU and that the revocation TIM supersedes the original version</i>	-	-
11.	Begin driving	The vehicles will drive the same path as in Step 5	-	-
12.	Observe TIM	Observers should note whether they received the TIM and any unexpected results as this is an edge case	OBU's receive the Weather Warning TIM and display the correct TIM image	Pass/Fail
13.	Repeat	Repeat Steps 5-12 for the following participant	-	-

14.7.1 Test Case Matrix

Table 29: Test Case Matrix

Weather Warning TIM	Participant RSUs	WYDOT (ISS)	WYDOT (Autocrypt)	CDOT	GDOT	UDOT	THEA
Participant OBUs	-	-	-	-	-	-	-
WYDOT (ISS)	-	-	-	-	-	-	-
WYDOT (Autocrypt)	-	-	-	-	-	-	-
CDOT	-	-	-	-	-	-	-
GDOT	-	-	-	-	-	-	-
UDOT	-	-	-	-	-	-	-
THEA	-	-	-	-	-	-	-
DENSO	-	-	-	-	-	-	-

14.8 Edge Case: TIM Update to a Different Message Type With Same ID

Table 30: TIM Update to Message Type Test Procedures

ID	Step	Action	Expected Result	Pass/Investigate/Fail
1.	Verify TIM readiness	Verify that start time and duration has been configured to broadcast the TIMs	-	-
2.	Deploy TIM	Deploy the Weather Warning TIM to the RSU	-	-
3.	Sign TIM	The deployment agency will sign the TIM using their protocol	RSUs correctly broadcast the Weather Warning TIM	Pass/Fail
4.	Begin driving	The participant vehicles will start driving at the top of the oval track from the north most roundabout, traveling counterclockwise around the oval	-	-
5.	Observe TIM	Observers will note the Weather Warning TIM as it appears on the HMI as the vehicle enters the geofence by taking a picture or screenshot of the TIM image	OBU's receive the Weather Warning TIM and display the correct TIM image	Pass/Fail
6.	Note TIM time and location	Observers will note the approximate time and location when the TIM appears	-	-
7.	Return to Laramie County Office	The vehicles will return to the office to download data and prepare for the next portion of the test	-	-
8.	Change original TIM	Change the TIM to a Work Zone Warning without changing the ID	-	-
9.	<i>Note</i>	<i>Vehicles may need to remain running to ensure the original TIM remains on the OBU and that the revocation TIM supersedes the original version</i>	-	-
10.	Begin driving	The vehicles will drive the same path as in Step 4	-	-
11.	Observe TIM	Observers should note whether they receive the expected Work Zone TIM or the original Weather Warning TIM	OBU's receive the Work Zone TIM and display the correct TIM image	Pass/Fail
12.	Repeat	Repeat Steps 4-12 for the following participant	-	-

14.8.1 Test Case Matrix

Table 31: Test Case Matrix

Weather Warning TIM	Participant RSUs	WYDOT (ISS)	WYDOT (Autocrypt)	CDOT	GDOT	UDOT	THEA
Participant OBUs	-	-	-	-	-	-	-
WYDOT (ISS)	-	-	-	-	-	-	-
WYDOT (Autocrypt)	-	-	-	-	-	-	-
CDOT	-	-	-	-	-	-	-
GDOT	-	-	-	-	-	-	-
UDOT	-	-	-	-	-	-	-
THEA	-	-	-	-	-	-	-
DENSO	-	-	-	-	-	-	-

14.9 Edge Case TIM: Message Priority

Table 32: TIM Message Priority Test Procedures

ID	Step	Action	Expected Result	Pass/Investigate/Fail
1.	Create Two TIMs	Create two versions (V1 and V2) of a Variable Speed Limit TIM and assign a priority of 0 to both	-	-
2.	Verify TIM readiness	Verify that start time and duration has been configured to broadcast the TIMs	-	-
3.	Deploy TIM	Deploy both TIMs to the RSU	-	-

ID	Step	Action	Expected Result	Pass/Investigate/ Fail
4.	Sign TIM	The deployment agency will sign the TIMs using their protocol	RSUs correctly broadcast the Weather Warning TIM	Pass/Fail
5.	Begin driving	The participant vehicles will start driving at the top of the oval track from the north most roundabout, traveling counterclockwise around the oval	-	-
6.	Observe TIM	Observers will note the Variable Speed Limit TIM as it appears on the HMI as the vehicle enters the geofence by taking a picture or screenshot of the TIM image	OBU receive the Variable Speed TIM and display the correct TIM image	Pass/Fail
7.	Note TIM time and location	Observers will note the approximate time and location when the TIM appears	-	-
8.	Return to Laramie County Office	The vehicles will return to the office to download data and prepare for the next portion of the test	-	-
9.	Change original TIM	Change the priority of the V2 TIM from 0 to 7 (this TIM is now considered V3)	-	-
10.	Resend TIM	Participant will resend both TIMs to the RSU	-	-
11.	<i>Note</i>	<i>Vehicles may need to remain running to ensure the original TIM remains on the OBU and that the revocation TIM supersedes the original version</i>	-	-
12.	Begin driving	The vehicles will drive the same path as in Step 5	-	-
13.	Observe TIM	Observers should note that they receive a Variable Speed Limit TIM. If observers can see the logs, they should identify which version (V1 or V3) and the priority of the message	OBU receive the Variable Speed Limit TIM and display the correct TIM image	Pass/Fail
14.	Return to Laramie County Office	The vehicles will return to the office to download data and prepare for the next portion of the test	-	-
15.	Change original TIM	Swap the priorities of the two TIMs. V1 now has a priority of 7 and V3 has a priority of 0.	-	-
16.	Resend TIM	Participant will resend both TIMs to the RSU	-	-
17.	Begin driving	The vehicles will drive the same path as in Step 5	-	-
18.	Observe TIM	Observers should note that they receive a Variable Speed Limit TIM. If observers can see the logs, they should identify which version (V1 or V3) and the priority of the message	OBU receive the Variable Speed Limit TIM and display the correct TIM image	Pass/Fail

14.9.1 Test Case Matrix

Table 33: Test Case Matrix

Weather Warning TIM	Participant RSUs	WYDOT (ISS)	WYDOT (Autocrypt)	CDOT	GDOT	UDOT	THEA
Participant OBUs	-	-	-	-	-	-	-
WYDOT (ISS)	-	-	-	-	-	-	-
WYDOT (Autocrypt)	-	-	-	-	-	-	-
CDOT	-	-	-	-	-	-	-
GDOT	-	-	-	-	-	-	-
UDOT	-	-	-	-	-	-	-
THEA	-	-	-	-	-	-	-
DENSO	-	-	-	-	-	-	-

15 Modifications Made to Test Plans and Procedures

During the execution of testing, there is the possibility that the details of some aspects of the test plan might have to be changed. Changes will be made at the discretion of the Test Sponsor and Test Director, with inputs from the test participants.

Modifications:

1. Timing of testing – originally, it was thought that it would take an hour per test run. This timing turned out to be too long, so a compressed schedule was used and is provided in section 11.
2. Edge cases – multiple edge cases were tested during the course of the interoperability test. These edge cases and the corresponding test procedures were added to sections 13 and 14.
3. Test equipment – the test equipment was updated based on the final equipment brought to the testing by the participants.
4. Data – an AWS S3 bucket was created and hosted by Leidos and USDOT for participants to add data packets from the testing. This is included in section 5.4.

16 Post Test Analysis

Analysis will be conducted in the weeks following testing to review the OBU log files. Log files will be analyzed to validate the reception of each TIM. The time and location will be noted from the log files as part of the analysis. This data will be uploaded to the ITS Data Hub after the completion of this analysis. Section 2.5 provides the minimum requirements for data collection and logging.

Appendix A: Acronyms

Table 34: Acronyms

Acronym	Definition
ASD	Aftermarket Safety Device
ASN.1	Abstract Syntax Notation One
BSM	Basic Safety Message
CDOT	Colorado Department of Transportation
CTI	Connected Transport Interoperability
CV	Connected Vehicle
CVP	Connected Vehicle Pilot
DSRC	Dedicated Short Range Communication
EMI	Electromagnetic Interference
ERDW	End of Ramp Deceleration Warning
FCW	Forward Collision Warning
GDOT	Georgia Department of Transportation
GPS	Global Positioning System
I2V	Infrastructure to Vehicle
IOO	Infrastructure Owner Operator
IMA	Intersection Movement Assist
ISS	Integrity Security Services
ITIS	International Traveler Information Systems
ITWG	Interoperability Technical Working Group
JPO	Joint Program Office
MEC	Mobile Edge Computing
MUTCD	Manual on Uniform Traffic Control Devices
NHTSA	National Highway Traffic Safety Administration
OBU	On-Board Unit
PII	Personally Identifiable Information
PCW	Pedestrian Crash Warning
RSM	Road Safety Message
RSU	Roadside Unit
SAE	Society of Automotive Engineers
SCMS	Security Credential Management System
SNMP	Simple Network Management Protocol
STOL	Saxton Transportation Operations Laboratory
TFHRC	Turner-Fairbank Highway Research Center
THEA	Tampa Hillsborough Expressway Authority
TIM	Traveler Information Message

Acronym	Definition
TRR	Test Readiness Review
UDOT	Utah Department of Transportation
USDOT	United States Department of Transportation
V2I	Vehicle to Infrastructure
V2V	Vehicle to Vehicle
V2X	Vehicle to Everything
VSL	Variable Speed Limit
WYDOT	Wyoming Department of Transportation

17 TIM JSON Files

1. RSU 2100 (Commsignia) Speed Limit (interop-speedlimit-d0-v1.json)

```
{  
  "request": {  
    "rsus": [  
      {  
        "rsuIndex": "31",  
        "rsuTarget": "127.0.0.1",  
        "rsuUsername": "rwUser",  
        "rsuPassword": "snmppassword",  
        "rsuRetries": "3",  
        "rsuTimeout": "5000"  
      }  
    ],  
    "snmp": {  
      "rsuid": "83",  
      "msgid": "31",  
      "mode": "1",  
      "channel": "183",  
      "interval": "1000",  
      "deliverystart": "2024-10-01T10:00:00.0Z",  
      "deliverystop": "2024-10-01T10:00:00.0Z",  
      "enable": "1",  
      "status": "4"  
    }  
  }  
}
```

```
},
"tim": {
  "msgCnt": "1",
  "timeStamp": "2024-10-01T10:00:00.0Z",
  "packetID": "8D44FF2100FFD00B01",
  "urlB": "null",
  "dataframes": [
    {
      "startDateTime": "2024-10-06T00:00:00.000Z",
      "durationTime": 8640,
      "sspTimRights": "0",
      "frameType": "advisory",
      "msgId": {
        "roadSignID": {
          "mutcdCode": "warning",
          "viewAngle": "1111111111111111",
          "position": {
            "latitude": "41.1513384",
            "longitude": "-104.6444217"
          }
        }
      }
    },
  ],
  "priority": "5",
  "sspLocationRights": "0",
  "regions": [
```

```
{
  "name": "SL D0 55 Arch Q4.1",
  "anchorPosition": {
    "latitude": "41.1513384",
    "longitude": "-104.6444217"
  },
  "laneWidth": "50",
  "directionality": "3",
  "closedPath": "false",
  "description": "path",
  "path": {
    "nodes": [
      {
        "nodeLong": "-0.0000390",
        "nodeLat": "0.0000979",
        "delta": "node-LL"
      },
      {
        "nodeLong": "-0.0000520",
        "nodeLat": "0.0001665",
        "delta": "node-LL"
      },
      {
        "nodeLong": "-0.0001301",
        "nodeLat": "0.0001959",
        "delta": "node-LL"
      },
      {
```

```
"nodeLong": "-0.0002081",  
"nodeLat": "0.0002252",  
"delta": "node-LL"  
},  
{  
"nodeLong": "-0.0002991",  
"nodeLat": "0.0002057",  
"delta": "node-LL"  
},  
{  
"nodeLong": "-0.0004032",  
"nodeLat": "0.0002350",  
"delta": "node-LL"  
},  
{  
"nodeLong": "-0.0004682",  
"nodeLat": "0.0002350",  
"delta": "node-LL"  
},  
{  
"nodeLong": "-0.0004812",  
"nodeLat": "0.0002154",  
"delta": "node-LL"  
},  
{
```

```
        "nodeLong": "-0.0005983",
        "nodeLat": "0.0002350",
        "delta": "node-LL"
    }
],
"type": "II",
"scale": "0"
},
"direction": "0000000000001111"
},
{
"name": "SL D0 55 Arch Q4.2",
"anchorPosition": {
    "latitude": "41.15315006",
    "longitude": "-104.64710095"
},
"laneWidth": "50",
"directionality": "3",
"closedPath": "false",
"description": "path",
"path": {
    "nodes": [
        {
            "nodeLong": "-0.0005853",
            "nodeLat": "0.0002057",
            "delta": "node-LL"
        },
    ]
},
}
```

```
"nodeLong": "-0.0008454",  
"nodeLat": "0.0001861",  
"delta": "node-LL"  
},  
{  
"nodeLong": "-0.0009494",  
"nodeLat": "0.0001469",  
"delta": "node-LL"  
},  
{  
"nodeLong": "-0.0011835",  
"nodeLat": "0.0001175",  
"delta": "node-LL"  
},  
{  
"nodeLong": "-0.0010405",  
"nodeLat": "0.0000490",  
"delta": "node-LL"  
},  
{  
"nodeLong": "-0.0007283",  
"nodeLat": "0.0000196",  
"delta": "node-LL"  
},  
{
```

```
        "nodeLong": "-0.0007413",
        "nodeLat": "0.0000000",
        "delta": "node-LL"
    }

],
    "type": "ll",
    "scale": "0"
},
    "direction": "0000000000001111"
}

],
    "sspMsgTypes": "0",
    "sspMsgContent": "0",
    "content": "speedLimit",
    "items": [
        "268", "12599", "8720"
    ],
    "url": "null"
}
]
}
}
```

2. RSU 2100 (Commsignia) Speed Limit v2 (interop-speedlimit-d0-v2.json)

```
{
  "request": {
    "rsus": [
      {
        "rsuIndex": "31",
        "rsuTarget": "127.0.0.1",
        "rsuUsername": "rwUser",
        "rsuPassword": "snmppassword",
        "rsuRetries": "3",
        "rsuTimeout": "5000"
      }
    ],
    "snmp": {
      "rsuid": "83",
      "msgid": "31",
      "mode": "1",
      "channel": "183",
      "interval": "1000",
      "deliverystart": "2024-10-01T10:00:00.0Z",
      "deliverystop": "2024-10-01T10:00:00.0Z",
      "enable": "1",
      "status": "4"
    }
  }
}
```

```
},
"tim": {
  "msgCnt": "2",
  "timeStamp": "2024-10-06T00:00:00.0Z",
  "packetID": "8D44FF2100FFD00B01",
  "urlB": "null",
  "dataframes": [
    {
      "startDateTime": "2024-10-06T00:00:00.000Z",
      "durationTime": 8640,
      "sspTimRights": "0",
      "frameType": "advisory",
      "msgId": {
        "roadSignID": {
          "mutcdCode": "warning",
          "viewAngle": "1111111111111111",
          "position": {
            "latitude": "41.1513384",
            "longitude": "-104.6444217"
          }
        }
      }
    },
  ],
  "priority": "5",
  "sspLocationRights": "0",
  "regions": [
    {
      "name": "SL D0 45 Arch Q4.1",
      "anchorPosition": {
```

```
"latitude": "41.1513384",  
"longitude": "-104.6444217"  
  
},  
  
"laneWidth": "50",  
  
"directionality": "3",  
  
"closedPath": "false",  
  
"description": "path",  
  
"path": {  
  "nodes": [  
    {  
      "nodeLong": "-0.0000390",  
      "nodeLat": "0.0000979",  
      "delta": "node-LL"  
    },  
    {  
      "nodeLong": "-0.0000520",  
      "nodeLat": "0.0001665",  
      "delta": "node-LL"  
    },  
    {  
      "nodeLong": "-0.0001301",  
      "nodeLat": "0.0001959",  
      "delta": "node-LL"  
    },  
    {
```

```
"nodeLong": "-0.0002081",
"nodeLat": "0.0002252",
"delta": "node-LL"
},
{
"nodeLong": "-0.0002991",
"nodeLat": "0.0002057",
"delta": "node-LL"
},
{
"nodeLong": "-0.0004032",
"nodeLat": "0.0002350",
"delta": "node-LL"
},
{
"nodeLong": "-0.0004682",
"nodeLat": "0.0002350",
"delta": "node-LL"
},
{
"nodeLong": "-0.0004812",
"nodeLat": "0.0002154",
"delta": "node-LL"
},
{
"nodeLong": "-0.0005983",
"nodeLat": "0.0002350",
"delta": "node-LL"
}
```

```
    }
  ],
  "type": "II",
  "scale": "0"
},
"direction": "0000000000001111"
},
{
  "name": "SL D0 45 Arch Q4.2",
  "anchorPosition": {
    "latitude": "41.15315006",
    "longitude": "-104.64710095"
  },
  "laneWidth": "50",
  "directionality": "3",
  "closedPath": "false",
  "description": "path",
  "path": {
    "nodes": [
      {
        "nodeLong": "-0.0005853",
        "nodeLat": "0.0002057",
        "delta": "node-LL"
      },
      {

```

```
"nodeLong": "-0.0008454",
"nodeLat": "0.0001861",
"delta": "node-LL"
},
{
"nodeLong": "-0.0009494",
"nodeLat": "0.0001469",
"delta": "node-LL"
},
{
"nodeLong": "-0.0011835",
"nodeLat": "0.0001175",
"delta": "node-LL"
},
{
"nodeLong": "-0.0010405",
"nodeLat": "0.0000490",
"delta": "node-LL"
},
{
"nodeLong": "-0.0007283",
"nodeLat": "0.0000196",
"delta": "node-LL"
},
{
"nodeLong": "-0.0007413",
"nodeLat": "0.0000000",
"delta": "node-LL"
}
```

```
    }

    ],

    "type": "II",

    "scale": "0"

  },

  "direction": "0000000000001111"

}

],

"sspMsgTypes": "0",

"sspMsgContent": "0",

"content": "speedLimit",

"items": [

  "268", "12589", "8720"

],

"url": "null"

}

]

}

}
```

3. RSU 2100 (Commsignia) Speed Limit 2 v2 (interop-speedlimit2-d10-v2.json)

```
{
  "request": {
    "rsus": [
      {
        "rsuIndex": "32",
        "rsuTarget": "127.0.0.1",
        "rsuUsername": "rwUser",
        "rsuPassword": "snmppassword",
        "rsuRetries": "3",
        "rsuTimeout": "5000"
      }
    ],
    "snmp": {
      "rsuid": "83",
      "msgid": "31",
      "mode": "1",
      "channel": "183",
      "interval": "1000",
      "deliverystart": "2024-10-01T10:00:00.0Z",
      "deliverystop": "2024-10-01T10:00:00.0Z",
      "enable": "1",
      "status": "4"
    }
  },
}
```

```
"tim": {
  "msgCnt": "2",
  "timeStamp": "2024-10-06T00:00:00.0Z",
  "packetID": "8D44FF2100FFD00B21",
  "urlB": "null",
  "dataframes": [
    {
      "startDateTime": "2024-10-06T00:00:00.000Z",
      "durationTime": 8640,
      "sspTimRights": "0",
      "frameType": "advisory",
      "msgId": {
        "roadSignID": {
          "mutcdCode": "warning",
          "viewAngle": "1111111111111111",
          "position": {
            "latitude": "41.1513384",
            "longitude": "-104.6444217"
          }
        }
      }
    },
    {
      "priority": "0",
      "sspLocationRights": "0",
      "regions": [
        {
```

```
"name": "SL D0 45 Arch Q4.1",
"anchorPosition": {
  "latitude": "41.1513384",
  "longitude": "-104.6444217"
},
"laneWidth": "50",
"directionality": "3",
"closedPath": "false",
"description": "path",
"path": {
  "nodes": [
    {
      "nodeLong": "-0.0000390",
      "nodeLat": "0.0000979",
      "delta": "node-LL"
    },
    {
      "nodeLong": "-0.0000520",
      "nodeLat": "0.0001665",
      "delta": "node-LL"
    },
    {
      "nodeLong": "-0.0001301",
      "nodeLat": "0.0001959",
      "delta": "node-LL"
    },
    {
      "nodeLong": "-0.0002081",
```

```
"nodeLat": "0.0002252",  
  "delta": "node-LL"  
},  
{  
  "nodeLong": "-0.0002991",  
  "nodeLat": "0.0002057",  
  "delta": "node-LL"  
},  
{  
  "nodeLong": "-0.0004032",  
  "nodeLat": "0.0002350",  
  "delta": "node-LL"  
},  
{  
  "nodeLong": "-0.0004682",  
  "nodeLat": "0.0002350",  
  "delta": "node-LL"  
},  
{  
  "nodeLong": "-0.0004812",  
  "nodeLat": "0.0002154",  
  "delta": "node-LL"  
},  
{  
  "nodeLong": "-0.0005983",
```

```
        "nodeLat": "0.0002350",
        "delta": "node-LL"
    }
],
    "type": "II",
    "scale": "0"
},
"direction": "0000000000001111"
},
{
    "name": "SL D0 45 Arch Q4.2",
    "anchorPosition": {
        "latitude": "41.15315006",
        "longitude": "-104.64710095"
    },
    "laneWidth": "50",
    "directionality": "3",
    "closedPath": "false",
    "description": "path",
    "path": {
        "nodes": [
            {
                "nodeLong": "-0.0005853",
                "nodeLat": "0.0002057",
                "delta": "node-LL"
            },
            {
                "nodeLong": "-0.0008454",
```

```
"nodeLat": "0.0001861",  
  "delta": "node-LL"  
},  
{  
  "nodeLong": "-0.0009494",  
  "nodeLat": "0.0001469",  
  "delta": "node-LL"  
},  
{  
  "nodeLong": "-0.0011835",  
  "nodeLat": "0.0001175",  
  "delta": "node-LL"  
},  
{  
  "nodeLong": "-0.0010405",  
  "nodeLat": "0.0000490",  
  "delta": "node-LL"  
},  
{  
  "nodeLong": "-0.0007283",  
  "nodeLat": "0.0000196",  
  "delta": "node-LL"  
},  
{  
  "nodeLong": "-0.0007413",
```

```
        "nodeLat": "0.000000",
        "delta": "node-LL"
    }

    ],
    "type": "II",
    "scale": "0"
},
"direction": "0000000000001111"
}

],
"sspMsgTypes": "0",
"sspMsgContent": "0",
"content": "speedLimit",
"items": [
    "268", "12589", "8720"
],
"url": "null"
}
]
}
}
```

4. RSU 2100 (Commsignia) Speed Limit 2 v3 (interop-speedlimit2-d10-v3.json)

```
{
  "request": {
    "rsus": [
      {
        "rsuIndex": "32",
        "rsuTarget": "127.0.0.1",
        "rsuUsername": "rwUser",
        "rsuPassword": "snmppassword",
        "rsuRetries": "3",
        "rsuTimeout": "5000"
      }
    ],
    "snmp": {
      "rsuid": "83",
      "msgid": "31",
      "mode": "1",
      "channel": "183",
      "interval": "1000",
      "deliverystart": "2024-10-01T10:00:00.0Z",
      "deliverystop": "2024-10-01T10:00:00.0Z",
      "enable": "1",
      "status": "4"
    }
  }
}
```

```
}  
},  
"tim": {  
  "msgCnt": "3",  
  "timeStamp": "2024-10-06T00:00:00.0Z",  
  "packetID": "8D44FF2100FFD00B21",  
  "urlB": "null",  
  "dataframes": [  
    {  
      "startDateTime": "2024-10-06T00:00:00.000Z",  
      "durationTime": 8640,  
      "sspTimRights": "0",  
      "frameType": "advisory",  
      "msgId": {  
        "roadSignID": {  
          "mutcdCode": "warning",  
          "viewAngle": "1111111111111111",  
          "position": {  
            "latitude": "41.1513384",  
            "longitude": "-104.6444217"  
          }  
        }  
      }  
    },  
  ],  
  "priority": "7",  
  "sspLocationRights": "0",  
  "regions": [  
    {  
      "name": "SL D0 45 Arch Q4.1",
```

```
"anchorPosition": {
  "latitude": "41.1513384",
  "longitude": "-104.6444217"
},
"laneWidth": "50",
"directionality": "3",
"closedPath": "false",
"description": "path",
"path": {
  "nodes": [
    {
      "nodeLong": "-0.0000390",
      "nodeLat": "0.0000979",
      "delta": "node-LL"
    },
    {
      "nodeLong": "-0.0000520",
      "nodeLat": "0.0001665",
      "delta": "node-LL"
    },
    {
      "nodeLong": "-0.0001301",
      "nodeLat": "0.0001959",
      "delta": "node-LL"
    }
  ],
}
```

```
{
  "nodeLong": "-0.0002081",
  "nodeLat": "0.0002252",
  "delta": "node-LL"
},
{
  "nodeLong": "-0.0002991",
  "nodeLat": "0.0002057",
  "delta": "node-LL"
},
{
  "nodeLong": "-0.0004032",
  "nodeLat": "0.0002350",
  "delta": "node-LL"
},
{
  "nodeLong": "-0.0004682",
  "nodeLat": "0.0002350",
  "delta": "node-LL"
},
{
  "nodeLong": "-0.0004812",
  "nodeLat": "0.0002154",
  "delta": "node-LL"
},
{
  "nodeLong": "-0.0005983",
  "nodeLat": "0.0002350",
```

```
        "delta": "node-LL"
      }
    ],
    "type": "II",
    "scale": "0"
  },
  "direction": "0000000000001111"
},
{
  "name": "SL D0 45 Arch Q4.2",
  "anchorPosition": {
    "latitude": "41.15315006",
    "longitude": "-104.64710095"
  },
  "laneWidth": "50",
  "directionality": "3",
  "closedPath": "false",
  "description": "path",
  "path": {
    "nodes": [
      {
        "nodeLong": "-0.0005853",
        "nodeLat": "0.0002057",
        "delta": "node-LL"
      }
    ],
  },
}
```

```
{
  "nodeLong": "-0.0008454",
  "nodeLat": "0.0001861",
  "delta": "node-LL"
},
{
  "nodeLong": "-0.0009494",
  "nodeLat": "0.0001469",
  "delta": "node-LL"
},
{
  "nodeLong": "-0.0011835",
  "nodeLat": "0.0001175",
  "delta": "node-LL"
},
{
  "nodeLong": "-0.0010405",
  "nodeLat": "0.0000490",
  "delta": "node-LL"
},
{
  "nodeLong": "-0.0007283",
  "nodeLat": "0.0000196",
  "delta": "node-LL"
},
{
  "nodeLong": "-0.0007413",
  "nodeLat": "0.0000000",
```

```
        "delta": "node-LL"
      }

    ],
    "type": "II",
    "scale": "0"
  },
  "direction": "0000000000001111"
}

],
"sspMsgTypes": "0",
"sspMsgContent": "0",
"content": "speedLimit",
"items": [
  "268", "12589", "8720"
],
"url": "null"
}
]
}
}
```

5. RSU 2100 (Commsignia) Weather v1 (interop-weather-d0-v1.json)

```
{
  "request": {
    "rsus": [
      {
        "rsuIndex": "21",
        "rsuTarget": "120.0.0.1",
        "rsuUsername": "rwUser",
        "rsuPassword": "snmppassword",
        "rsuRetries": "3",
        "rsuTimeout": "5000"
      }
    ],
    "snmp": {
      "rsuid": "83",
      "msgid": "31",
      "mode": "1",
      "channel": "183",
      "interval": "1000",
      "deliverystart": "2024-10-06T10:00:00.0Z",
      "deliverystop": "2024-10-20T10:00:00.0Z",
      "enable": "1",
      "status": "4"
    }
  },
}
```

```
"tim": {
  "msgCnt": "1",
  "timeStamp": "2024-10-06T00:00:00.0Z",
  "packetID": "8D44FF2100FFD00A01",
  "urlB": "null",
  "dataframes": [
    {
      "startDateTime": "2024-10-06T00:00:00.000Z",
      "durationTime": 8640,
      "sspTimRights": "0",
      "frameType": "advisory",
      "msgId": {
        "roadSignID": {
          "mutcdCode": "warning",
          "viewAngle": "1111111111111111",
          "position": {
            "latitude": "41.153400",
            "longitude": "-104.657587"
          }
        }
      }
    },
    {
      "priority": "5",
      "sspLocationRights": "0",
      "regions": [
        {
```

```
"name": "W2100 D0 Snow ArchQ1",
"anchorPosition": {
  "latitude": "41.153400",
  "longitude": "-104.657587"
},
"laneWidth": "50",
"directionality": "3",
"closedPath": "false",
"description": "path",
"path": {
  "nodes": [
    {
      "nodeLong": "-0.0000906",
      "nodeLat": "-0.0000227",
      "delta": "node-LL"
    },
    {
      "nodeLong": "-0.0007088",
      "nodeLat": "-0.0001334",
      "delta": "node-LL"
    },
    {
      "nodeLong": "-0.0005907",
      "nodeLat": "-0.0001186",
      "delta": "node-LL"
    },
    {
      "nodeLong": "-0.0006104",
```

```
"nodeLat": "-0.0001631",  
  "delta": "node-LL"  
},  
{  
  "nodeLong": "-0.0006695",  
  "nodeLat": "-0.0002076",  
  "delta": "node-LL"  
},  
{  
  "nodeLong": "-0.0005316",  
  "nodeLat": "-0.0002372",  
  "delta": "node-LL"  
},  
{  
  "nodeLong": "-0.0006301",  
  "nodeLat": "-0.0002817",  
  "delta": "node-LL"  
},  
{  
  "nodeLong": "-0.0004726",  
  "nodeLat": "-0.0002372",  
  "delta": "node-LL"  
},  
{  
  "nodeLong": "-0.0004529",
```

```
        "nodeLat": "-0.0002965",
        "delta": "node-LL"
    },
    {
        "nodeLong": "-0.0004135",
        "nodeLat": "-0.0002817",
        "delta": "node-LL"
    }
],
"type": "II",
"scale": "0"
},
"direction": "1111000011110000"
}
],
"sspMsgTypes": "0",
"sspMsgContent": "0",
"content": "advisory",
"items": [
    "4868"
],
"url": "null"
}
]
}
}
```

6. RSU 2100 (Commsignia) Weather v2 (interop-weather-d07-v2.json)

```
{
  "request": {
    "rsus": [
      {
        "rsuIndex": "21",
        "rsuTarget": "120.0.0.1",
        "rsuUsername": "rwUser",
        "rsuPassword": "snmppassword",
        "rsuRetries": "3",
        "rsuTimeout": "5000"
      }
    ],
    "snmp": {
      "rsuid": "83",
      "msgid": "31",
      "mode": "1",
      "channel": "183",
      "interval": "1000",
      "deliverystart": "2024-10-06T10:00:00.0Z",
      "deliverystop": "2024-10-20T10:00:00.0Z",
      "enable": "1",
      "status": "4"
    }
  }
}
```

```
}
},
"tim": {
  "msgCnt": "2",
  "timeStamp": "2024-10-06T00:00:00.0Z",
  "packetID": "8D44FF2100FFD00A01",
  "urlB": "null",
  "dataframes": [
    {
      "startDateTime": "2024-10-07T00:00:00.000Z",
      "durationTime": 1260,
      "sspTimRights": "0",
      "frameType": "advisory",
      "msgId": {
        "roadSignID": {
          "mutcdCode": "warning",
          "viewAngle": "1111111111111111",
          "position": {
            "latitude": "41.153400",
            "longitude": "-104.657587"
          }
        }
      }
    },
  ],
  "priority": "5",
  "sspLocationRights": "0",
  "regions": [
    {
      "name": "W2100 D0 Snow ArchQ1",
```

```
"anchorPosition": {
  "latitude": "41.153400",
  "longitude": "-104.657587"
},
"laneWidth": "50",
"directionality": "3",
"closedPath": "false",
"description": "path",
"path": {
  "nodes": [
    {
      "nodeLong": "-0.0000906",
      "nodeLat": "-0.0000227",
      "delta": "node-LL"
    },
    {
      "nodeLong": "-0.0007088",
      "nodeLat": "-0.0001334",
      "delta": "node-LL"
    },
    {
      "nodeLong": "-0.0005907",
      "nodeLat": "-0.0001186",
      "delta": "node-LL"
    }
  ],

```

```
{
  "nodeLong": "-0.0006104",
  "nodeLat": "-0.0001631",
  "delta": "node-LL"
},
{
  "nodeLong": "-0.0006695",
  "nodeLat": "-0.0002076",
  "delta": "node-LL"
},
{
  "nodeLong": "-0.0005316",
  "nodeLat": "-0.0002372",
  "delta": "node-LL"
},
{
  "nodeLong": "-0.0006301",
  "nodeLat": "-0.0002817",
  "delta": "node-LL"
},
{
  "nodeLong": "-0.0004726",
  "nodeLat": "-0.0002372",
  "delta": "node-LL"
},
{
  "nodeLong": "-0.0004529",
  "nodeLat": "-0.0002965",
```

```
        "delta": "node-LL"
      },
      {
        "nodeLong": "-0.0004135",
        "nodeLat": "-0.0002817",
        "delta": "node-LL"
      }
    ],
    "type": "ll",
    "scale": "0"
  },
  "direction": "1111000011110000"
}
],
"sspMsgTypes": "0",
"sspMsgContent": "0",
"content": "advisory",
"items": [
  "4868"
],
"url": "null"
}
]
}
}
```

7. RSU 2100 (Commsignia) Workzone-Reduced Speed v1 (interop-workzone-reducedspeed-d0-v1.json)

```
{
  "request": {
    "rsus": [
      {
        "rsuIndex": "41",
        "rsuTarget": "127.0.0.1",
        "rsuUsername": "rwUser",
        "rsuPassword": "snmppassword",
        "rsuRetries": "3",
        "rsuTimeout": "5000"
      }
    ],
    "snmp": {
      "rsuid": "83",
      "msgid": "31",
      "mode": "1",
      "channel": "183",
      "interval": "1000",
      "deliverystart": "2024-10-01T10:00:00.0Z",
      "deliverystop": "2024-10-20T10:00:00.0Z",
      "enable": "1",
      "status": "4"
    }
  },
}
```

```
"tim": {
  "msgCnt": "1",
  "timeStamp": "2024-10-01T10:00:00.0Z",
  "packetID": "8D44FF2100FFD00C01",
  "urlB": "null",
  "dataframes": [
    {
      "startDateTime": "2024-10-06T00:00:00.000Z",
      "durationTime": 8640,
      "sspTimRights": "0",
      "frameType": "advisory",
      "msgId": {
        "roadSignID": {
          "mutcdCode": "warning",
          "viewAngle": "1111111111111111",
          "position": {
            "latitude": "41.1472587",
            "longitude": "-104.6513098"
          }
        }
      }
    },
    {
      "priority": "5",
      "sspLocationRights": "0",
      "regions": [
        {
```

```
"name": "RSZ D0 45 Arch Q23",
"anchorPosition": {
  "latitude": "41.1472587",
  "longitude": "-104.6513098"
},
"laneWidth": "50",
"directionality": "3",
"closedPath": "false",
"description": "path",
"path": {
  "nodes": [
    {
      "nodeLong": "0.0001274",
      "nodeLat": "0.0000326",
      "delta": "node-LL"
    },
    {
      "nodeLong": "0.0005944",
      "nodeLat": "0.0000910",
      "delta": "node-LL"
    },
    {
      "nodeLong": "0.0007052",
      "nodeLat": "0.0001517",
      "delta": "node-LL"
    },
    {
      "nodeLong": "0.0010678",
```

```
"nodeLat": "0.0002427",  
  "delta": "node-LL"  
},  
{  
  "nodeLong": "0.0010074",  
  "nodeLat": "0.0002958",  
  "delta": "node-LL"  
},  
{  
  "nodeLong": "0.0006548",  
  "nodeLat": "0.0002579",  
  "delta": "node-LL"  
},  
{  
  "nodeLong": "0.0006649",  
  "nodeLat": "0.0003034",  
  "delta": "node-LL"  
},  
{  
  "nodeLong": "0.0005742",  
  "nodeLat": "0.0003414",  
  "delta": "node-LL"  
},  
{  
  "nodeLong": "0.0003627",
```

```
        "nodeLat": "0.0002807",
        "delta": "node-LL"
    },
    {
        "nodeLong": "0.0002821",
        "nodeLat": "0.0001972",
        "delta": "node-LL"
    }
],
"type": "II",
"scale": "0"
},
"direction": "0111000000000000"
}
],
"sspMsgTypes": "0",
"sspMsgContent": "0",
"content": "speedLimit",
"items": [
    "268","12589","8720"
],
"url": "null"
},
{
"startDateTime": "2024-10-06T00:00:00.000Z",
"durationTime": 8640,
"sspTimRights": "0",
"frameType": "advisory",
```

```
"msgId": {
  "roadSignID": {
    "mutcdCode": "warning",
    "viewAngle": "1111111111111111",
    "position": {
      "latitude": "41.14899435",
      "longitude": "-104.6633312"
    }
  }
},
"priority": "5",
"sspLocationRights": "0",
"regions": [
  {
    "name": "RSZ D0 45 Ahead Archer Q23",
    "anchorPosition": {
      "latitude": "41.14899435",
      "longitude": "-104.6633312"
    },
    "laneWidth": "50",
    "directionality": "3",
    "closedPath": "false",
    "description": "path",
    "path": {
      "nodes": [
```

```
{
  "nodeLong": "0.0000602",
  "nodeLat": "-0.0001024",
  "delta": "node-LL"
},
{
  "nodeLong": "0.0004332",
  "nodeLat": "-0.0003414",
  "delta": "node-LL"
},
{
  "nodeLong": "0.0006145",
  "nodeLat": "-0.0003414",
  "delta": "node-LL"
},
{
  "nodeLong": "0.0006649",
  "nodeLat": "-0.0003034",
  "delta": "node-LL"
},
{
  "nodeLong": "0.0007455",
  "nodeLat": "-0.0002579",
  "delta": "node-LL"
},
{
  "nodeLong": "0.0009268",
  "nodeLat": "-0.0002579",
```

```
    "delta": "node-LL"
  },
  {
    "nodeLong": "0.0011081",
    "nodeLat": "-0.0002124",
    "delta": "node-LL"
  },
  {
    "nodeLong": "0.0011686",
    "nodeLat": "-0.0001062",
    "delta": "node-LL"
  },
  {
    "nodeLong": "0.0012189",
    "nodeLat": "-0.0000683",
    "delta": "node-LL"
  },
  {
    "nodeLong": "0.0013499",
    "nodeLat": "-0.0000152",
    "delta": "node-LL"
  },
  {
    "nodeLong": "0.0014406",
    "nodeLat": "0.0000379",
```

```
        "delta": "node-LL"
      },
      {
        "nodeLong": "0.0011484",
        "nodeLat": "0.0001138",
        "delta": "node-LL"
      },
      {
        "nodeLong": "0.0010376",
        "nodeLat": "0.0001365",
        "delta": "node-LL"
      }
    ],
    "type": "ll",
    "scale": "0"
  },
  "direction": "0011111000000000"
}
],
"sspMsgTypes": "0",
"sspMsgContent": "0",
"content": "speedLimit",
"items": [
  "268","12302","12589","8720","13569"
],
"url": "null"
}
]
```

```
}  
}
```

8. RSU 2100 (Commsignia) Workzone-Reduced Speed v2 (interop-workzone-reducedspeed-d07-v2.json)

```
{  
  "request": {  
    "rsus": [  
      {  
        "rsuIndex": "41",  
        "rsuTarget": "127.0.0.1",  
        "rsuUsername": "rwUser",  
        "rsuPassword": "snmppassword",  
        "rsuRetries": "3",  
        "rsuTimeout": "5000"  
      }  
    ],  
    "snmp": {  
      "rsuid": "83",  
      "msgid": "31",  
      "mode": "1",  
      "channel": "183",  
      "interval": "1000",  
      "deliverystart": "2024-10-01T10:00:00.0Z",  
      "deliverystop": "2024-10-20T10:00:00.0Z",
```

```
"enable": "1",
"status": "4"
}
},
"tim": {
  "msgCnt": "2",
  "timeStamp": "2024-10-01T10:00:00.0Z",
  "packetID": "8D44FF2100FFD00C01",
  "urlB": "null",
  "dataframes": [
    {
      "startDateTime": "2024-10-07T00:00:00.000Z",
      "durationTime": 1290,
      "sspTimRights": "0",
      "frameType": "advisory",
      "msgId": {
        "roadSignID": {
          "mutcdCode": "warning",
          "viewAngle": "1111111111111111",
          "position": {
            "latitude": "41.1472587",
            "longitude": "-104.6513098"
          }
        }
      }
    },
  ],
  "priority": "5",
  "sspLocationRights": "0",
  "regions": [
```

```
{
  "name": "RSZ D0 45 Arch Q23",
  "anchorPosition": {
    "latitude": "41.1472587",
    "longitude": "-104.6513098"
  },
  "laneWidth": "50",
  "directionality": "3",
  "closedPath": "false",
  "description": "path",
  "path": {
    "nodes": [
      {
        "nodeLong": "0.0001274",
        "nodeLat": "0.0000326",
        "delta": "node-LL"
      },
      {
        "nodeLong": "0.0005944",
        "nodeLat": "0.0000910",
        "delta": "node-LL"
      },
      {
        "nodeLong": "0.0007052",
        "nodeLat": "0.0001517",
```

```
    "delta": "node-LL"
  },
  {
    "nodeLong": "0.0010678",
    "nodeLat": "0.0002427",
    "delta": "node-LL"
  },
  {
    "nodeLong": "0.0010074",
    "nodeLat": "0.0002958",
    "delta": "node-LL"
  },
  {
    "nodeLong": "0.0006548",
    "nodeLat": "0.0002579",
    "delta": "node-LL"
  },
  {
    "nodeLong": "0.0006649",
    "nodeLat": "0.0003034",
    "delta": "node-LL"
  },
  {
    "nodeLong": "0.0005742",
    "nodeLat": "0.0003414",
    "delta": "node-LL"
  },
  {
```

```
        "nodeLong": "0.0003627",
        "nodeLat": "0.0002807",
        "delta": "node-LL"
    },
    {
        "nodeLong": "0.0002821",
        "nodeLat": "0.0001972",
        "delta": "node-LL"
    }
],
"type": "II",
"scale": "0"
},
"direction": "0111000000000000"
}
],
"sspMsgTypes": "0",
"sspMsgContent": "0",
"content": "speedLimit",
"items": [
    "268","12589","8720"
],
"url": "null"
},
{
```

```
"startDateTime": "2024-10-07T00:00:00.000Z",
"durationTime": 1290,
"sspTimRights": "0",
"frameType": "advisory",
"msgId": {
  "roadSignID": {
    "mutcdCode": "warning",
    "viewAngle": "1111111111111111",
    "position": {
      "latitude": "41.14899435",
      "longitude": "-104.6633312"
    }
  }
},
"priority": "5",
"sspLocationRights": "0",
"regions": [
  {
    "name": "RSZ D0 45 Ahead Archer Q23",
    "anchorPosition": {
      "latitude": "41.14899435",
      "longitude": "-104.6633312"
    },
    "laneWidth": "50",
    "directionality": "3",
    "closedPath": "false",
    "description": "path",
    "path": {
```

```
"nodes": [  
  {  
    "nodeLong": "0.0000602",  
    "nodeLat": "-0.0001024",  
    "delta": "node-LL"  
  },  
  {  
    "nodeLong": "0.0004332",  
    "nodeLat": "-0.0003414",  
    "delta": "node-LL"  
  },  
  {  
    "nodeLong": "0.0006145",  
    "nodeLat": "-0.0003414",  
    "delta": "node-LL"  
  },  
  {  
    "nodeLong": "0.0006649",  
    "nodeLat": "-0.0003034",  
    "delta": "node-LL"  
  },  
  {  
    "nodeLong": "0.0007455",  
    "nodeLat": "-0.0002579",  
    "delta": "node-LL"  
  }  
]
```

```
  },
  {
    "nodeLong": "0.0009268",
    "nodeLat": "-0.0002579",
    "delta": "node-LL"
  },
  {
    "nodeLong": "0.0011081",
    "nodeLat": "-0.0002124",
    "delta": "node-LL"
  },
  {
    "nodeLong": "0.0011686",
    "nodeLat": "-0.0001062",
    "delta": "node-LL"
  },
  {
    "nodeLong": "0.0012189",
    "nodeLat": "-0.0000683",
    "delta": "node-LL"
  },
  {
    "nodeLong": "0.0013499",
    "nodeLat": "-0.0000152",
    "delta": "node-LL"
  },
  {
    "nodeLong": "0.0014406",
```

```
        "nodeLat": "0.0000379",
        "delta": "node-LL"
    },
    {
        "nodeLong": "0.0011484",
        "nodeLat": "0.0001138",
        "delta": "node-LL"
    },
    {
        "nodeLong": "0.0010376",
        "nodeLat": "0.0001365",
        "delta": "node-LL"
    }
],
"type": "II",
"scale": "0"
},
"direction": "0011111000000000"
}
],
"sspMsgTypes": "0",
"sspMsgContent": "0",
"content": "speedLimit",
"items": [
    "268","12302","12589","8720","13569"
```

```
    ],
    "url": "null"
  }
]
}
}
```

9. RSU 2100 (Commsignia) Workzone-Right Lane Closed v1 (interop-workzone-rightlaneclosed-d0-v1.json)

```
{
  "request": {
    "rsus": [
      {
        "rsuIndex": "42",
        "rsuTarget": "127.0.0.1",
        "rsuUsername": "rwUser",
        "rsuPassword": "snmppassword",
        "rsuRetries": "3",
        "rsuTimeout": "5000"
      }
    ],
    "snmp": {
      "rsuid": "83",
      "msgid": "31",
      "mode": "1",
      "channel": "183",
      "interval": "1000",
      "deliverystart": "2024-10-01T10:00:00.0Z",

```

```
"deliverystop": "2024-10-20T10:00:00.0Z",
"enable": "1",
"status": "4"
}
},
"tim": {
  "msgCnt": "1",
  "timeStamp": "2024-10-02T00:00:00.0Z",
  "packetID": "8D44FF2100FFD00C02",
  "urlB": "null",
  "dataframes": [
    {
      "startDateTime": "2024-10-06T00:00:00.000Z",
      "durationTime": 8640,
      "sspTimRights": "0",
      "frameType": "advisory",
      "msgId": {
        "roadSignID": {
          "mutcdCode": "warning",
          "viewAngle": "1111111111111111",
          "position": {
            "latitude": "41.147205668",
            "longitude": "-104.6590462"
          }
        }
      }
    }
  ]
}
```

```
},
"priority": "5",
"sspLocationRights": "0",
"regions": [
  {
    "name": "LC D0 RightLaneClosed Arch Q23",
    "anchorPosition": {
      "latitude": "41.147205668",
      "longitude": "-104.6590462"
    },
    "laneWidth": "50",
    "directionality": "3",
    "closedPath": "false",
    "description": "path",
    "path": {
      "nodes": [
        {
          "nodeLong": "0.0000503",
          "nodeLat": "-0.0000152",
          "delta": "node-LL"
        },
        {
          "nodeLong": "0.0013096",
          "nodeLat": "-0.0001214",
          "delta": "node-LL"
        },
        {
          "nodeLong": "0.0012693",
```

```
    "nodeLat": "-0.0000683",  
    "delta": "node-LL"  
  },  
  {  
    "nodeLong": "0.0014003",  
    "nodeLat": "-0.0000152",  
    "delta": "node-LL"  
  },  
  {  
    "nodeLong": "0.0009570",  
    "nodeLat": "0.0000152",  
    "delta": "node-LL"  
  },  
  {  
    "nodeLong": "0.0009268",  
    "nodeLat": "0.0000607",  
    "delta": "node-LL"  
  },  
  {  
    "nodeLong": "0.0009469",  
    "nodeLat": "0.0001138",  
    "delta": "node-LL"  
  },  
  {  
    "nodeLong": "0.0011484",
```

```
        "nodeLat": "0.0001365",
        "delta": "node-LL"
    },
    {
        "nodeLong": "0.0007354",
        "nodeLat": "0.0001214",
        "delta": "node-LL"
    },
    {
        "nodeLong": "0.0007555",
        "nodeLat": "0.0001517",
        "delta": "node-LL"
    }
],
"type": "II",
"scale": "0"
},
"direction": "0011110000000000"
}
],
"sspMsgTypes": "0",
"sspMsgContent": "0",
"content": "workZone",
"items": [
    "8196","771"
],
"url": "null"
}
```

```
]
}
}
```

10. RSU 2100 (Commsignia) Workzone-Right Lane Closed v2 (interop-workzone-rightlaneclosed-d07-v2.json)

```
{
  "request": {
    "rsus": [
      {
        "rsuIndex": "42",
        "rsuTarget": "127.0.0.1",
        "rsuUsername": "rwUser",
        "rsuPassword": "snmppassword",
        "rsuRetries": "3",
        "rsuTimeout": "5000"
      }
    ],
    "snmp": {
      "rsuid": "83",
      "msgid": "31",
      "mode": "1",
      "channel": "183",
      "interval": "1000",
      "deliverystart": "2024-10-01T10:00:00.0Z",

```

```
"deliverystop": "2024-10-20T10:00:00.0Z",
"enable": "1",
"status": "4"
}
},
"tim": {
  "msgCnt": "2",
  "timeStamp": "2024-10-02T00:00:00.0Z",
  "packetID": "8D44FF2100FFD00C02",
  "urlB": "null",
  "dataframes": [
    {
      "startDateTime": "2024-10-07T00:00:00.000Z",
      "durationTime": 1290,
      "sspTimRights": "0",
      "frameType": "advisory",
      "msgId": {
        "roadSignID": {
          "mutcdCode": "warning",
          "viewAngle": "1111111111111111",
          "position": {
            "latitude": "41.147205668",
            "longitude": "-104.6590462"
          }
        }
      }
    },
  ],
  "priority": "5",
  "sspLocationRights": "0",
```

```
"regions": [  
  {  
    "name": "LC D0 RightLaneClosed Arch Q23",  
    "anchorPosition": {  
      "latitude": "41.147205668",  
      "longitude": "-104.6590462"  
    },  
    "laneWidth": "50",  
    "directionality": "3",  
    "closedPath": "false",  
    "description": "path",  
    "path": {  
      "nodes": [  
        {  
          "nodeLong": "0.0000503",  
          "nodeLat": "-0.0000152",  
          "delta": "node-LL"  
        },  
        {  
          "nodeLong": "0.0013096",  
          "nodeLat": "-0.0001214",  
          "delta": "node-LL"  
        },  
        {  
          "nodeLong": "0.0012693",
```

```
    "nodeLat": "-0.0000683",
    "delta": "node-LL"
  },
  {
    "nodeLong": "0.0014003",
    "nodeLat": "-0.0000152",
    "delta": "node-LL"
  },
  {
    "nodeLong": "0.0009570",
    "nodeLat": "0.0000152",
    "delta": "node-LL"
  },
  {
    "nodeLong": "0.0009268",
    "nodeLat": "0.0000607",
    "delta": "node-LL"
  },
  {
    "nodeLong": "0.0009469",
    "nodeLat": "0.0001138",
    "delta": "node-LL"
  },
  {
    "nodeLong": "0.0011484",
    "nodeLat": "0.0001365",
    "delta": "node-LL"
  },
}
```

```
    {
      "nodeLong": "0.0007354",
      "nodeLat": "0.0001214",
      "delta": "node-LL"
    },
    {
      "nodeLong": "0.0007555",
      "nodeLat": "0.0001517",
      "delta": "node-LL"
    }
  ],
  "type": "II",
  "scale": "0"
},
"direction": "0011110000000000"
}
],
"sspMsgTypes": "0",
"sspMsgContent": "0",
"content": "workZone",
"items": [
  "8196","771"
],
"url": "null"
}
```

```
    ]  
  }  
}
```

11. RSU 2100 (Commsignia) Workzone-Workzone v1 (interop-workzone-workzone-d0-v1.json)

```
{  
  "request": {  
    "rsus": [  
      {  
        "rsuIndex": "43",  
        "rsuTarget": "127.0.0.1",  
        "rsuUsername": "rwUser",  
        "rsuPassword": "snmppassword",  
        "rsuRetries": "3",  
        "rsuTimeout": "5000"  
      }  
    ],  
    "snmp": {  
      "rsuid": "83",  
      "msgid": "31",  
      "mode": "1",  
      "channel": "183",  
      "interval": "1000",  
      "deliverystart": "2024-10-01T10:00:00.0Z",  
      "deliverystop": "2024-10-20T10:00:00.0Z",  
      "enable": "1",  
      "status": "4"  
    }  
  }  
}
```

```
}
},
"tim": {
  "msgCnt": "1",
  "timeStamp": "2024-10-02T10:00:00.0Z",
  "packetID": "8D44FF2100FFD00C03",
  "urlB": "null",
  "dataframes": [
    {
      "startDateTime": "2024-10-06T00:00:00.000Z",
      "durationTime": 8640,
      "sspTimRights": "0",
      "frameType": "advisory",
      "msgId": {
        "roadSignID": {
          "mutcdCode": "warning",
          "viewAngle": "1111111111111111",
          "position": {
            "latitude": "41.14760015",
            "longitude": "-104.6494761"
          }
        }
      }
    },
  ],
  "priority": "5",
  "sspLocationRights": "0",
```

```
"regions": [  
  {  
    "name": "WZ D0 Arch Q3",  
    "anchorPosition": {  
      "latitude": "41.14760015",  
      "longitude": "-104.6494761"  
    },  
    "laneWidth": "50",  
    "directionality": "3",  
    "closedPath": "false",  
    "description": "path",  
    "path": {  
      "nodes": [  
        {  
          "nodeLong": "0.0000403",  
          "nodeLat": "-0.0000000",  
          "delta": "node-LL"  
        },  
        {  
          "nodeLong": "0.0005843",  
          "nodeLat": "0.0001441",  
          "delta": "node-LL"  
        },  
        {  
          "nodeLong": "0.0007455",  
          "nodeLat": "0.0002200",  
          "delta": "node-LL"  
        }  
      ]  
    }  
  }  
]
```

```
{
  "nodeLong": "0.0006447",
  "nodeLat": "0.0002276",
  "delta": "node-LL"
},
{
  "nodeLong": "0.0007354",
  "nodeLat": "0.0003186",
  "delta": "node-LL"
},
{
  "nodeLong": "0.0004533",
  "nodeLat": "0.0002427",
  "delta": "node-LL"
}
],
"type": "II",
"scale": "0"
},
"direction": "0111000000000000"
}
],
"sspMsgTypes": "0",
"sspMsgContent": "0",
"content": "workZone",
```

```
    "items": [  
      "1025"  
    ],  
    "url": "null"  
  }  
]  
}  
}
```

12. RSU 2100 (Commsignia) Workzone-Workzone v2 (interop-workzone-workzone-d07-v2.json)

```
{  
  "request": {  
    "rsus": [  
      {  
        "rsuIndex": "43",  
        "rsuTarget": "127.0.0.1",  
        "rsuUsername": "rwUser",  
        "rsuPassword": "snmppassword",  
        "rsuRetries": "3",  
        "rsuTimeout": "5000"  
      }  
    ],  
    "snmp": {  
      "rsuid": "83",  
      "msgid": "31",  
      "mode": "1",  
      "channel": "183",
```

```
"interval": "1000",
"deliverystart": "2024-10-01T10:00:00.0Z",
"deliverystop": "2024-10-20T10:00:00.0Z",
"enable": "1",
"status": "4"
}
},
"tim": {
  "msgCnt": "2",
  "timeStamp": "2024-10-02T10:00:00.0Z",
  "packetID": "8D44FF2100FFD00C03",
  "urlB": "null",
  "dataframes": [
    {
      "startDateTime": "2024-10-07T00:00:00.000Z",
      "durationTime": 1290,
      "sspTimRights": "0",
      "frameType": "advisory",
      "msgId": {
        "roadSignID": {
          "mutcdCode": "warning",
          "viewAngle": "1111111111111111",
          "position": {
            "latitude": "41.14760015",
            "longitude": "-104.6494761"
```

```
    }
  }
},
"priority": "5",
"sspLocationRights": "0",
"regions": [
  {
    "name": "WZ D0 Arch Q3",
    "anchorPosition": {
      "latitude": "41.14760015",
      "longitude": "-104.6494761"
    },
    "laneWidth": "50",
    "directionality": "3",
    "closedPath": "false",
    "description": "path",
    "path": {
      "nodes": [
        {
          "nodeLong": "0.0000403",
          "nodeLat": "-0.0000000",
          "delta": "node-LL"
        },
        {
          "nodeLong": "0.0005843",
          "nodeLat": "0.0001441",
          "delta": "node-LL"
        }
      ],
    }
  }
]
```

```
{
  "nodeLong": "0.0007455",
  "nodeLat": "0.0002200",
  "delta": "node-LL"
},
{
  "nodeLong": "0.0006447",
  "nodeLat": "0.0002276",
  "delta": "node-LL"
},
{
  "nodeLong": "0.0007354",
  "nodeLat": "0.0003186",
  "delta": "node-LL"
},
{
  "nodeLong": "0.0004533",
  "nodeLat": "0.0002427",
  "delta": "node-LL"
}
],
"type": "ll",
"scale": "0"
},
"direction": "0111000000000000"
```

```
    }
  ],
  "sspMsgTypes": "0",
  "sspMsgContent": "0",
  "content": "workZone",
  "items": [
    "1025"
  ],
  "url": "null"
}
]
}
}
```

U.S. Department of Transportation
ITS Joint Program Office – HOIT
1200 New Jersey Avenue, SE
Washington, DC 20590

Toll-Free “Help Line” 866-367-7487

www.its.dot.gov

[FHWA-JPO-24-148]



U.S. Department of Transportation

U.S. Department of Transportation
Office of the Assistant Secretary for Research and Technology
Intelligent Transportation Systems Joint Program Office